

Request for Quotation

RFQ Title: Current renovation of the tasting room and office premises of the career guidance hub at the Municipal Institution “Chernihiv Vocational and Technical Education Center” of the Chernihiv Regional Council

Date of Solicitation: 04/08/2025

Submission Date and time: 08/08/2025 no later than 15:00 Kyiv time

Questions and Clarifications Due by: 07/08/2025

Запит цінових пропозицій

Назва ЗЦП: Поточний ремонт дегустаційної зали та службових приміщень профорієнтаційного хабу у Комунальному закладі “Чернігівський центр професійно-технічної освіти” Чернігівської обласної ради

Дата конкурсу: 04.08.2025

Дата і час подання: 08.08.2025 не пізніше 15:00 за київським часом

Поставити питання та зробити уточнення можна до: 07.08.2025

Request for Quotation (RFQ)

regarding the procurement of services for the current repair of the tasting room and staff premises of the Career Guidance Hub at the Municipal Institution “Chernihiv Center for Vocational Education” of the Chernihiv Regional Council

NGO “Development of Citizenship Competencies in Ukraine” (NGO “DOCCU”) within the framework of the project “Support to the reform of vocational education in Ukraine” of the Swiss-Ukrainian DECIDE Project is conducting a **procurement services for the current renovation of the tasting room and office premises of the career guidance hub at the Municipal Institution “Chernihiv Vocational and Technical Education Center” of the Chernihiv Regional Council.**

Place and period of service provision: Chernihiv city, Kozatska st., building 7a.

Instructions for submitting a request for quote

Business entities duly registered under the Legislation of Ukraine, with experience in the relevant field, corresponding to the KVED, are invited to participate in the procurement.

Запит цінових пропозицій (ЗЦП)

щодо закупівлі послуги з поточного ремонту дегустаційної зали та службових приміщень профорієнтаційного хабу у Комунальному закладі “Чернігівський центр професійно-технічної освіти” Чернігівської обласної ради

Громадська організація «Розвиток громадянських компетентностей в Україні» (ГО «ДОККУ») в межах напряму “Підтримка реформи професійної освіти в Україні” Швейцарсько-українського Проєкту DECIDE проводить закупівлю **послуги з поточного ремонту дегустаційної зали та службових приміщень профорієнтаційного хабу у Комунальному закладі “Чернігівський центр професійно-технічної освіти” Чернігівської обласної ради.**

Місце і строк надання послуг: м. Чернігів, вул. Козацька, буд. 7а

Інструкція з подання цінової пропозиції

До участі у закупівлі запрошуються суб’єкти підприємницької діяльності, належним чином зареєстровані за Законодавством України, які мають досвід роботи у відповідній сфері, відповідні КВЕД.

The candidate must include the following information in the proposal:

- Appendix No. 1 Letter - response (Attached);
- Appendix No. 2 Letter of notification regarding the absence of open proceedings in a bankruptcy case, etc. (Attached);
- Copies of documents confirming the registration of a legal entity or an individual entrepreneur. (Copies of an extract from the Unified State Register of Legal Entities and Individual Entrepreneurs; Copies of an extract from the Unified State Register of Legal Entities and Individual Entrepreneurs with an indication of KVED; Copies of the single tax payer's certificate).
- Bank certificate on opening a current account.

Submission of proposal in electronic format

Proposals in electronic document format must be sent to the specified address by **August 8, 2025 (inclusive), no later than 15:00 Kyiv time.**

Submissions must be made exclusively in electronic format (PDF, Microsoft Word or Excel) to procurement@doccu.org.ua. Suppliers should not send archived files. Pages with original handwritten signatures must be scanned and sent in PDF format as an e-mail attachment.

In the subject line of the letter, please indicate: "Request for quotations for the purchase of current repair services".

Offers received after the specified time or to a different email address may not be accepted.

Evaluation criteria

Evaluation component	Weight	The maximum number of points you can get
Proven experience in performing similar work	40%	40
Completeness and	20%	20

Кандидат повинен включити в пропозицію таку інформацію:

- Додаток №1 Лист – відповідь (Додається);
- Додаток №2 Лист-повідомлення щодо відсутності відкритих проваджень у справі про банкрутство, тощо (Додається);
- Копії документів, що підтверджують реєстрацію юридичної особи чи фізичної особи-підприємця. (Копії виписки з Єдиного державного реєстру юридичних осіб та фізичних осіб-підприємців; Копії витягу з Єдиного державного реєстру юридичних осіб та фізичних осіб-підприємців із зазначенням КВЕД; Копії свідоцтва платника єдиного податку).
- Довідка з банку про відкриття поточного рахунку.

Подання пропозиції в електронному форматі

Пропозиції у форматі електронних документів повинні бути надіслані на зазначену адресу до **08 серпня 2025 року (включно), не пізніше 15:00 за київським часом.**

Подання мають здійснюватися виключно в електронному форматі (PDF, Microsoft Word або Excel) на адресу procurement@doccu.org.ua. Постачальники не повинні надсилати архівовані файли. Сторінки, на яких мають стояти оригінальні власноручні підписи, треба відсканувати і відправити у форматі PDF як додаток до електронного листа.

В темі листа просимо зазначити: «Запит цінкових пропозицій щодо закупівлі послуги з поточного ремонту».

Пропозиції отримані після зазначеного часу або за іншою електронною адресою можуть не прийматися.

Критерії оцінювання

Складова оцінки	Вага	Максимальна кількість балів, які можна отримати

correctness of the submitted documents			Підтверджений досвід виконання подібних робіт	40%	40
Financial criterion	40%	40	Повнота та правильність поданих документів	20%	20
Total	100%	100	Фінансовий критерій	40%	40
			Всього	100%	100

Технічне завдання

№ п/п	Найменування робіт та витрат	Одиниця виміру	Кількість	Примітка
1	2	3	4	5
-	<u>Локальний кошторис 02-01-01 на Приміщення №2</u>	-	-	-
-	-	-	-	-
-	<u>Розділ 1. Прорізи</u>	-	-	-
-	-	-	-	-
1	Демонтаж дверних коробок в кам'яних стінах з відбиванням штукатурки в укосах	шт	1	
2	Знімання дверних полотен	м2	1,95	
3	Знімання наличників	м	10,2	
4	Заповнення дверних прорізів готовими дверними блоками площею понад 2 до 3 м2 з металопластику у кам'яних стінах	м2	2,01	
5	Блоки дверні металопластикові зі склом (колір графіт)	м2	2,01	
6	Піна монтажна Ceresit	шт	0,5	
7	Анкер 150мм	шт	7	
8	Установлення і кріплення наличників	м	5,3	
9	Наличники (колір графіт)	м	5,936	
10	Рідкі цвяхи Faiger 280 мл Прозорий	шт	1	
11	Установлення дотягувача	шт	1	
12	Дотягувач(колір графіт)	шт	1	
-	<u>Розділ 2. Стеля</u>	-	-	-
-	-	-	-	-
13	Улаштування каркасу підвісних стель	м2	17,5	
14	Профіль поперечний (направляючий) 3,6 м Armstrong	м	16,63	Обсяг в ДЦ був заданий арифметично м виразом $r2(0,95 \times 34,6)$.

15	Профіль для підвісної стелі 1,2 м Armstrong	м	33,25	Обсяг в ДЦ був заданий арифметичним виразом $r2(1,9 \times 34,6)$.
16	Профіль для підвісної стелі 0,6 м Armstrong	м	16,63	Обсяг в ДЦ був заданий арифметичним виразом $r2(0,95 \times 34,6)$.
17	Профіль кутовий пристінний	м	18,9	Обсяг в ДЦ був заданий арифметичним виразом $r2(1,08 \times 34,6)$.
1	2	3	4	5
18	Підвіс для стелі в зборі	шт	14	Обсяг в ДЦ був заданий арифметичним виразом $r0(0,8 \times 34,6)$.
19	Тяга підвісу	шт	14	Обсяг в ДЦ був заданий арифметичним виразом $r0(0,8 \times 34,6)$.
20	Дюбель 6/40	шт	52	
21	Влаштування плит стельових в каркас стелі "Армстронг"	м2	16,78	
22	Плита підвісної стелі Armstrong	м2	17,619	Обсяг в ДЦ був заданий арифметичним виразом $34,6 \times 1,02$.
Розділ 3. Стіни		-	-	-
-	-	-	-	-
23	Улаштування основи під штукатурку з металевої сітки по цегляних та бетонних поверхнях	м2	45,6	
24	Сітка металева 15x20	м2	50,16	
25	Ремонт штукатурки внутрішніх стін по каменю та бетону цементною сумішшю	м2	45,6	
26	Штукатурка цементна Ceresit	кг	775,2	
27	Облицювання поверхонь стін керамічними плитками на розчині із сухої клеючої суміші	м2	29,6	
28	Плитка настінна	м2	29,9	
29	Грунтівка Бетоноконтакт	л	10,36	
30	Клей для плитки Ceresit CM 11	кг	115,44	
31	Хрестики для плитки	шт	304	
32	Фуґа Ceresit CE 33	кг	14,68	
33	Шпаклювання стін мінеральною шпаклівкою	м2	16	
34	Грунтовка Ceresit СТ-17	л	3,2	
35	Шпаклівка Start Knauf	кг	28,8	
36	Додавати на 1 мм зміни товщини шпаклівки до норм 15-182-1, 15-182-2	м2	16	

37	Шпаклівка Knauf Super Finish	кг	28,8	
38	Поліпшене фарбування полівінілацетатними водоемульсійними сумішами стін по штукатурці	м2	16	
39	Латексна фарба Svart для стін та стелі	л	10,08	
	<u>Розділ 4. Підлоги</u>	-	-	-
-	-	-	-	-
40	Розбирання дерев'яних плінтусів	м	15,9	
41	Розбирання покриттів підлог з лінолеуму та реліну	м2	17,8	
42	Улаштування цементної стяжки товщиною 20 мм по бетонній основі площею до 20 м2(60мм)	м2	17,8	
43	На кожні 5 мм зміни товщини шару цементної стяжки додавати або виключати	м2	17,8	
44	Суміш Siltek F-20	кг	2136	
45	Улаштування покриттів з керамічних плиток на розчині із сухої клеючої суміші, кількість плиток в 1 м2 до 7 шт	м2	17,8	
46	Плитка Cersanit Флойд Лайт Грей Мат Ректифікат	м2	18,19	
47	Грунтівка Бетоноконтакт	л	6,23	
48	Клей для плитки Ceresit CM 11	кг	115,7	
49	Хрестики для плитки	шт	75	
50	Фуга Ceresit CE 33	кг	7,23	
	<u>Розділ 5. Оздоблення підвіконня</u>	-	-	-
-	-	-	-	-
51	Очищення вручну підвіконь від олійної, перхлорвінілової фарби	м2	0,85	
1	2	3	4	5
52	Грунтування поверхонь	м2	0,85	
53	Грунтувальна фарба Ceresit CT 16	л	0,43	
54	Обклеювання поверхонь склосіткою	м2	0,85	
55	Склосітка штукатурна лугостійка ССА-160 5х5 160 г/кв.м	м2	0,89	
56	Штукатурка Knauf Ротбанд	кг	3,61	
57	Суцільне вирівнювання бетонних поверхонь [одношарове штукатурення], товщина шару 10 мм	м2	0,85	
58	Штукатурка цементна Ceresit CT 24	кг	10,2	
59	Шпаклювання підвіконня мінеральною шпаклівкою	м2	0,85	
60	Грунтовка Ceresit CT-17	л	0,17	
61	Шпаклівка Start Knauf	кг	1,53	
62	Додавати на 1 мм зміни товщини шпаклівки до норм 15-182-1, 15-182-2	м2	0,85	
63	Шпаклівка Knauf Super Finish	кг	1,53	
64	Просте фарбування емаллю підвіконня по штукатурці та збірних конструкціях	м2	0,85	
	<u>Розділ 6. Електромонтажні роботи</u>	-	-	-
-	-	-	-	-
65	Демонтаж світильників	шт	2	
66	Демонтаж вимикачів, розеток	шт	3	
67	Монтаж світильників для люмінесцентних ламп, які встановлюються в підвісних стелях, кількість ламп 1 шт	шт	2	
68	Світильник для підвісної стелі 600х600	шт	2	
69	Установлення блоків з кількістю установлюваних апаратів [вимикачів і штепсельних розеток] до 3	шт	2	

70	Розетка подвійна 3/3	шт	2	
71	Коробка установча під бетон (100 шт)	шт	2	
72	Дюбелі 6x40	шт	4	
73	Установлення вимикачів утопленого типу при схованій проводці, 1-клавішних	шт	1	
74	Вимикач 1-кл Asfora білий	шт	1	
75	Коробка установча під бетон (100 шт)	шт	1	
76	Дюбелі 6x40	шт	2	
77	Влаштування штроб в цегляній стіні	м	5	
78	Прокладання проводів при схованій проводці в борознах	м	5	
79	ВВГ нг-LS-П 3х1,5 (5кл) (КУ) СІРИЙ	м	2,04	
80	ВВГ нг-LS-П 3х2,5 (5кл) (КУ) СІРИЙ	м	3,06	
81	Монтаж вініпластових труб для електропроводки діаметром до 25 мм	м	10	
82	1420 D K50D Труба гнучка с протяжкой 320 N (50м)	м	10,1	
83	Затягування першого проводу перерізом понад 2,5 мм2 до 6 мм2 в труби	м	10	
84	ВВГ нг-LS-П 3х1,5 (5кл) (КУ) СІРИЙ	м	5,1	
85	ВВГ нг-LS-П 3х2,5 (5кл) (КУ) СІРИЙ	м	5,1	
86	Заробка штроби шириною 2см, глибиною не більше 45мм	м	5	
87	Штукатурка цементна Ceresit	кг	0,5	
88	Свердлення отворів в цегляних стінах, товщина стін 0,5 цеглини, діаметр отвору до 20 мм	шт	3	
89	На кожні 10 мм діаметру отворів понад 20 мм додавати	шт	3	
	<u>Розділ 7. Сантехнічні роботи</u>	-	-	-
-	-	-	-	-
90	Демонтаж радіаторів масою до 80 кг	шт	4	
91	Установлення опалювальних радіаторів сталевих	кВт	0,808	
92	Опалювальний прилад біметалевий секційний DIVA 96/500 ВІ 4секц.	шт	1	
93	Настінне кріплення для радіаторів	шт	1	
94	Прокладання трубопроводів з труб поліетиленових [поліпропіленових] напірних діаметром 20 мм	м	1	
1	2	3	4	5
95	Труби KAN-therm PP stabIAL PPR SDR6 (PN20) 20x2,8 20x2,8 PP STABIAL PPR	м	1	
96	Під'єднання нових ділянок трубопроводу до існуючих мереж водопостачання чи опалення діаметром 15 мм	шт	2	
97	Різьба 1/2"	шт	2	
98	Муфта РВ 20x1/2	шт	4	
99	Установлення кранів діаметром до 25 мм	шт	3	
100	Кран шар. ЗР 1/2"	шт	2	
101	Кран маєвського	шт	1	
	<u>Розділ 8. Інше</u>	-	-	-
-	-	-	-	-
102	Обклеювання плоских поверхонь протиударною плівкою	м2	2,55	
103	Плівка протиударна	м2	2,6	
104	Розбирання сталевих повітроводів	м2	6,3	

105	Прокладання повітроводів периметром від 1100 мм до 1600 мм з листової сталі класу Н [нормальна] товщиною 0,7 мм	м2	3,5	
106	Фарбування олійними сумішами за 2 рази раніше пофарбованих сталевих труб	м2	0,9	
107	Очищення приміщень від сміття	т	2,08086	
108	Навантаження сміття вручну	т	1,95754	
109	Перевезення сміття до 30 км	т	1,95754	
	<u>Локальний кошторис 02-01-02 на Приміщення №1</u>	-	-	-
-	-	-	-	-
-	<u>Розділ 1. Прорізи</u>	-	-	-
-	-	-	-	-
110	Демонтаж дверних коробок в кам'яних стінах з відбиванням штукатурки в укусах	шт	1	
111	Знімання дверних полотен	м2	2	
112	Заповнення дверних прорізів готовими дверними блоками площею понад 2 до 3 м2 з металопластику у кам'яних стінах	м2	2,05	
113	Блоки дверні металопластикові зі склом (колір графіт)	м2	2,05	
114	Піна монтажна Ceresit	шт	0,5	
115	Анкер 150мм	шт	7	
116	Установлення і кріплення наличників	м	5,35	
117	Наличники (колір графіт)	м	5,992	
118	Рідкі цвяхи Faiger 280 мл Прозорий	шт	1	
119	Установлення дотягувача	шт	1	
120	Дотягувач(колір графіт)	шт	1	
	<u>Розділ 2. Оздоблення підвіконня</u>	-	-	-
-	-	-	-	-
121	Очищення вручну підвіконь від олійної, перхлорвінілової фарби	м2	0,85	
122	Грунтування поверхонь	м2	0,85	
123	Грунтувальна фарба Ceresit СТ 16	л	0,43	
124	Обклеювання поверхонь склосіткою	м2	0,85	
125	Склосітка штукатурна лугостійка ССА-160 5х5 160 г/кв.м	м2	0,89	
126	Штукатурка Кнауф Ротбанд	кг	3,61	
127	Суцільне вирівнювання бетонних поверхонь [одношарове штукатурення], товщина шару 10 мм	м2	0,85	
128	Штукатурка цементна Ceresit СТ 24	кг	10,2	
129	Шпаклювання підвіконня мінеральною шпаклівкою	м2	0,85	
130	Грунтовка Ceresit СТ-17	л	0,17	
131	Шпаклівка Start Knauf	кг	1,53	
132	Додавати на 1 мм зміни товщини шпаклівки до норм 15-182-1, 15-182-2	м2	0,85	
133	Шпаклівка Knauf Super Finish	кг	1,53	
134	Просте фарбування емаллю підвіконня по штукатурці та збірних конструкціях	м2	0,85	
1	2	3	4	5
-	<u>Розділ 3. Стеля</u>	-	-	-
-	-	-	-	-
135	Улаштування каркасу підвісних стель	м2	14,8	

136	Профіль поперечний (направляючий) 3,6 м Armstrong	м	14,06	Обсяг в ДЦ був заданий арифметични м виразом $r2(0,95 \times 34,6)$.
137	Профіль для підвісної стелі 1,2 м Armstrong	м	28,12	Обсяг в ДЦ був заданий арифметични м виразом $r2(1,9 \times 34,6)$.
138	Профіль для підвісної стелі 0,6 м Armstrong	м	14,06	Обсяг в ДЦ був заданий арифметични м виразом $r2(0,95 \times 34,6)$.
139	Профіль кутовий пристінний	м	15,98	Обсяг в ДЦ був заданий арифметични м виразом $r2(1,08 \times 34,6)$.
140	Підвіс для стелі в зборі	шт	12	Обсяг в ДЦ був заданий арифметични м виразом $r0(0,8 \times 34,6)$.
141	Тяга підвісу	шт	12	Обсяг в ДЦ був заданий арифметични м виразом $r0(0,8 \times 34,6)$.
142	Дюбель 6/40	шт	44	
143	Влаштування плит стельових в каркас стелі "Армстронг"	м2	14,08	
144	Плита підвісної стелі Armstrong	м2	14,784	Обсяг в ДЦ був заданий арифметични м виразом $34,6 \times 1,02$.
<u>Розділ 4. Стіни</u>		-	-	-
-	-	-	-	-
145	Ґрунтування поверхонь	м2	46,2	
146	Ґрунтувальна фарба Ceresit СТ 16	л	23,1	
147	Ремонт штукатурки внутрішніх стін по каменю та бетону цементною сумішшю	м2	13,9	
148	Штукатурка цементна Ceresit	кг	236,3	
149	Суцільне вирівнювання штукатурки стін усередині будівлі при товщині накиді до 10 мм	м2	27,2	
150	Штукатурка цементна Ceresit СТ 24	кг	326,4	
151	Обклеювання поверхонь склосіткою	м2	46,2	
152	Склосітка штукатурна лугостійка ССА-160 5х5 160 г/кв.м	м2	48,51	
153	Штукатурка Кнауф Ротбанд	кг	196,35	
154	Установлення перфорованих штукатурних кутиків	м	8,9	
155	Шпаклювання стін та короба мінеральною шпаклівкою	м2	46,2	
156	Ґрунтовка Ceresit СТ-17	л	9,24	
157	Шпаклівка Start Knauf	кг	83,16	

158	Додавати на 1 мм зміни товщини шпаклівки до норм 15-182-1, 15-182-2	м2	46,2	
159	Шпаклівка Knauf Super Finish	кг	83,16	
1	2	3	4	5
160	Поліпшене фарбування полівінілацетатними водоемульсійними сумішами стін та короба по штукатурці	м2	46,2	
161	Латексна фарба Svart для стін та стелі	л	29,11	
	<u>Розділ 5. Підлоги</u>	-	-	-
-	-	-	-	-
162	Розбирання дерев'яних плінтусів	м	13,4	
163	Розбирання покриттів підлог з лінолеуму та реліну	м2	15	
164	Розбирання покриттів підлог з полівінілхлоридних плиток	м2	15	
165	Розбирання смолянистих покриттів підлог	м2	15	
166	Грунтування поверхонь	м2	15	
167	Грунтівка Бетоноконтакт	л	5,25	
168	Улаштування цементної стяжки товщиною 20 мм по бетонній основі площею до 20 м2(80мм)	м2	15	
169	На кожні 5 мм зміни товщини шару цементної стяжки додавати або виключати	м2	15	
170	Суміш Siltek F-20	кг	2400	
171	Улаштування покриттів з керамічних плиток на розчині із сухої клеючої суміші, кількість плиток в 1 м2 до 7 шт	м2	15	
172	Плитка Cersanit Флойд Лайт Грей Мат Ректифікат	м2	15,3	
173	Грунтівка Бетоноконтакт	л	5,25	
174	Клей для плитки Ceresit CM 11	кг	97,5	
175	Хрестики для плитки	шт	64	
176	Фуга Ceresit CE 33	кг	6,09	
	<u>Розділ 6. Електромонтажні роботи</u>	-	-	-
-	-	-	-	-
177	Демонтаж світильників	шт	2	
178	Демонтаж вимикачів, розеток	шт	2	
179	Монтаж світильників для люмінесцентних ламп, які встановлюються в підвісних стелях, кількість ламп 1 шт	шт	2	
180	Світильник для підвісної стелі 600х600	шт	2	
181	Установлення блоків з кількістю установлюваних апаратів [вимикачів і штепсельних розеток] до 3	шт	1	
182	Розетка подвійна з/з	шт	1	
183	Коробка установча під бетон (100 шт)	шт	1	
184	Дюбелі 6х40	шт	2	
185	Установлення вимикачів утопленого типу при схованій проводці, 1-клавішних	шт	1	
186	Вимикач 1-кл Asfora білий	шт	1	
187	Коробка установча під бетон (100 шт)	шт	1	
188	Дюбелі 6х40	шт	2	
189	Влаштування штроб в цегляній стіні	м	4	
190	Прокладання проводів при схованій проводці в борознах	м	4	
191	ВВГ нг-LS-П 3х1,5 (5кл) (КУ) СІРИЙ	м	2,04	
192	ВВГ нг-LS-П 3х2,5 (5кл) (КУ) СІРИЙ	м	2,04	
193	Монтаж вініпластових труб для електропроводки діаметром до 25 мм	м	15	

194	1420 D K50D Труба гнучка с протяжкой 320 N (50м)	м	15,15	
195	Затягування першого проводу перерізом понад 2,5 мм2 до 6 мм2 в труби	м	15	
196	ВВГ нг-LS-П 3х1,5 (5кл) (КУ) СІРИЙ	м	10,2	
197	ВВГ нг-LS-П 3х2,5 (5кл) (КУ) СІРИЙ	м	5,1	
198	Заробка штробы шириною 2см, глибиною не більше 45мм	м	4	
199	Штукатурка цементна Ceresit	кг	0,4	
200	Свердлення отворів в цегляних стінах, товщина стін 0,5 цеглини, діаметр отвору до 20 мм	шт	2	
201	На кожні 10 мм діаметру отворів понад 20 мм додавати	шт	2	
	<u>Розділ 7. Сантехнічні роботи</u>	-	-	-
-	-	-	-	-
1	2	3	4	5
202	(Демонтаж) Установлення тумб	шт	1	
203	Демонтаж раковин [умивальників]	к-т	1	
204	Демонтаж змішувачів	шт	1	
205	(Демонтаж) Прокладання трубопроводу водопостачання з труб сталевих водогазопровідних оцинкованих діаметром 20 мм	м	3	
206	Розбирання трубопроводів з труб чавунних каналізаційних діаметром до 50 мм	м	0,6	
207	(Демонтаж) Прокладання трубопроводів каналізації з поліетиленових труб діаметром 50 мм	м	1	
208	Прокладання трубопроводів з труб поліетиленових [поліпропіленових] напірних діаметром 20 мм	м	1,5	
209	Труби KAN-therm PP stabIAL PPR SDR6 (PN20) 20x2,8 20x2,8 PP STABIAL PPR	м	1,5	
210	Перехідник (редукція) д.20	шт	1	
211	Кріплення для труб д.20	шт	3	
212	Установлення умивальників одиночних з підведенням холодної води	к-т	1	
213	Умивальник з тумбочкою	шт	1	
214	Сифон для умивальника	шт	1	
215	Гнучкий шланг	шт	1	
216	Установлення змішувачів	шт	1	
217	Змішувачі	шт	1	
218	Установлення муфтових кранів водорозбірних	шт	1	
219	Кран шар. 3Р 1/2"	шт	1	
220	Установлення сталевих заглушок на трубопроводі діаметром до 100 мм	заглушка	2	
221	Заглушка 1/2"	шт	2	
222	Установлення люка ревізійного	шт	1	
223	Люк ревізійний 200*200	шт	1	
224	Під'єднання нових ділянок трубопроводу до існуючих мереж водопостачання чи опалення діаметром 15 мм	шт	1	
225	Різьба 1/2"	шт	1	
226	Муфта РВ 20х1/2	шт	2	
227	Пробивання борозен в цегляних стінах	м	2,7	
228	Заробка штробы	м	2,7	
229	Штукатурка цементна Ceresit	кг	2,7	
230	Свердлення отворів в цегляних стінах	шт	3	

	<u>Розділ 8. Інше</u>	-	-	-
-	-	-	-	-
231	Обклеювання плоских поверхонь протиударною плівкою	м2	2,55	
232	Плівка протиударна	м2	2,6	
233	Фарбування олійними сумішами за 2 рази раніше пофарбованих радіаторів та ребристих труб	м2	3,33	
234	Фарбування олійними сумішами за 2 рази раніше пофарбованих сталевих труб	м2	0,14	
235	Очищення приміщень від сміття	т	1,29283	
236	Навантаження сміття вручну	т	1,76951	
237	Перевезення сміття до 30 км	т	1,76951	
	<u>Локальний кошторис 02-01-03 на Приміщення №5</u>	-	-	-
-	-	-	-	-
-	<u>Розділ 1. Прорізи</u>	-	-	-
-	-	-	-	-
238	Демонтаж дверних коробок в кам'яних стінах з відбиванням штукатурки в укосах	шт	1	
239	Знімання дверних полотен	м2	2	
240	Заповнення дверних прорізів готовими дверними блоками площею понад 2 до 3 м2 з металопластику у кам'яних стінах	м2	2,05	
241	Блоки дверні металопластикові зі склом (колір графіт)	м2	2,05	
1	2	3	4	5
242	Піна монтажна Ceresit	шт	0,5	
243	Анкер 150мм	шт	7	
244	Установлення і кріплення наличників	м	5,4	
245	Наличники (колір графіт)	м	6,048	
246	Рідкі цвяхи Faiger 280 мл Прозорий	шт	1	
247	Установлення дотягувача	шт	1	
248	Дотягувач(колір графіт)	шт	1	
	<u>Розділ 2. Стеля</u>	-	-	-
-	-	-	-	-
249	(Демонтаж) Обклеювання матеріалу натяжної стелі	м2	28	
250	(Демонтаж)Монтаж сталевих профілів	м	21,2	
251	(Демонтаж)каркасів конструкцій стель із дерев'яних брусів	м2	35,25	
252	Розбирання підвісних стель з плит азбоцементних	м2	35,25	
253	Розбирання багетів	м	21,3	
254	Демонтаж облицювання короба з гіпсокартона	м2	14,2	
255	Демонтаж каркасу короба	м2	14,2	
256	Улаштування каркасу підвісних стель	м2	35,25	
257	Укладання плит стельових "Грильято"в каркас стелі	м2	35,25	
258	Профіль Грильято верхній	шт	487	
259	Профіль Грильято нижній	шт	487	
260	Анкер-клін 60*40	шт	74	
261	Підвіс для стелі в зборі	шт	74	
				Обсяг в ДЦ був заданий арифметично м виразом r0(0,8x34,6).

262	Тяга підвісу	шт	74	Обсяг в ДЦ був заданий арифметични м виразом r0(0,8x34,6).
263	Дюбель 6x60	шт	105	
264	З`єднувач для Грильято	шт	23	
265	Профіль Грильято 0,6м	шт	98	
266	Профіль пристінний 2м	шт	12	
267	Профіль Грильято 2,4м	шт	25	
268	Промазування і розшивання швів панелей перекриття розчином знизу	м шва	35,4	
269	Грунтування поверхонь	м2	50,3	
270	Грунтовка Ceresit СТ-17	л	10,06	
271	Поліпшене фарбування чорною фарбою стель	м2	50,3	
272	Латексна фарба Svart для стін та стелі	л	34,71	
	<u>Розділ 3. Підлога</u>	-	-	-
-	-	-	-	-
273	Розбирання дерев'яних плінтусів	м	21,3	
274	Опорядження поверхні паркетних покриттів, що були в експлуатації	м2	36,8	
275	Шпаклівка Тіккуріла	л	5,89	
276	Лак Tikkurila	л	15,46	
277	Грунтовка Tikkurila	л	9,2	
278	Улаштування плінтусів дерев'яних з кріпленням шурупами	м	21,3	
279	Плінтус для підлоги	м	21,513	
280	Дюбель 6x60	шт	32	
	<u>Розділ 4. Стіни</u>	-	-	-
-	-	-	-	-
281	Знімання шпалер простих та поліпшених	м2	27,4	
282	Розбирання облицювання стін з плит вапняка	м2	2	
1	2	3	4	5
283	Облицювання поверхонь стін плитками на розчині із сухої клеючої суміші, число плиток в 1 м2 до 7 шт(раніше демонтованої)	м2	2	
284	Грунтівка Бетоноконтакт	л	0,7	
285	Клей для плитки Ceresit CM 11	кг	13	
286	Хрестики для плитки	шт	8	
287	Фура Ceresit CE 33	кг	0,81	
288	Грунтування поверхонь	м2	25,7	
289	Грунтовка Ceresit СТ-17	л	5,14	
290	Фарбування плитки	м2	25,7	
291	Латексна фарба Svart для стін та стелі	л	16,19	
292	Грунтування поверхонь	м2	43,1	
293	Грунтовка Ceresit СТ-17	л	8,62	
294	Ремонт штукатурки внутрішніх стін по каменю та бетону цементною сумішшю	м2	13	
295	Штукатурка цементна Ceresit	кг	221	
296	Суцільне вирівнювання штукатурки стін усередині будівлі при товщині накиді до 10 мм	м2	30,1	
297	Штукатурка цементна Ceresit СТ 24	кг	361,2	

298	Обклеювання поверхонь склосіткою	м2	43,1	
299	Склосітка штукатурна лугостійка ССА-160 5х5 160 г/кв.м	м2	45,26	
300	Штукатурка Knauf Ротбанд	кг	183,18	
301	Установлення перфорованих штукатурних кутиків	м	10,4	
302	Шпаклювання стін мінеральною шпаклівкою	м2	43,1	
303	Грунтовка Ceresit СТ-17	л	8,62	
304	Шпаклівка Start Knauf	кг	77,58	
305	Додавати на 1 мм зміни товщини шпаклівки до норм 15-182-1, 15-182-2	м2	43,1	
306	Шпаклівка Knauf Super Finish	кг	77,58	
307	Поліпшене фарбування полівінілацетатними водоемульсійними сумішами стін та короба по штукатурці	м2	43,1	
308	Латексна фарба Svart для стін та стелі	л	27,15	
	<u>Розділ 5. Оздоблення підвіконня</u>	-	-	-
309	Очищення вручну підвіконь від олійної, перхлорвінілової фарби	м2	1,7	
310	Грунтування поверхонь	м2	1,7	
311	Грунтувальна фарба Ceresit СТ 16	л	0,85	
312	Обклеювання поверхонь склосіткою	м2	1,7	
313	Склосітка штукатурна лугостійка ССА-160 5х5 160 г/кв.м	м2	1,79	
314	Штукатурка Knauf Ротбанд	кг	7,23	
315	Суцільне вирівнювання бетонних поверхонь [одношарове штукатурення], товщина шару 10 мм	м2	1,7	
316	Штукатурка цементна Ceresit СТ 24	кг	20,4	
317	Шпаклювання підвіконня мінеральною шпаклівкою	м2	1,7	
318	Грунтовка Ceresit СТ-17	л	0,34	
319	Шпаклівка Start Knauf	кг	3,06	
320	Додавати на 1 мм зміни товщини шпаклівки до норм 15-182-1, 15-182-2	м2	1,7	
321	Шпаклівка Knauf Super Finish	кг	3,06	
322	Просте фарбування емаллю підвіконня по штукатурці та збірних конструкціях	м2	1,7	
	<u>Розділ 6. Відкоси</u>	-	-	-
323	Відбивання штукатурки	м2	4,35	
324	Улаштування обшивки укосів гіпсокартонними і гіпсоволокнистими листами з кріпленням на клеї	м2	4,35	
325	Гіпсокартон вологостійкий Knauf	м2	4,5675	
326	Кутики перфоровані	м	16	
1	2	3	4	5
327	Клей для гіпсокартона Knauf PERLFIX	кг	21,75	
328	Шпаклювання відкосів мінеральною шпаклівкою	м2	4,35	
329	Грунтовка Ceresit СТ-17	л	0,87	
330	Додавати на 1 мм зміни товщини шпаклівки до норм 15-182-1, 15-182-2	м2	4,35	
331	Шпаклівка Knauf Super Finish	кг	15,66	
332	Поліпшене фарбування полівінілацетатними водоемульсійними сумішами відкосів по штукатурці	м2	4,35	

333	Латексна фарба Svart для стін та стелі	л	2,74	
	<u>Розділ 7. Електромонтажні роботи</u>	-	-	-
-	-	-	-	-
334	Демонтаж вимикачів, розеток	шт	4	
335	Демонтаж світильників світлодіодних	шт	4	
336	(Демонтаж) Монтаж люстри	шт	1	
337	Монтаж треків	шт	9	
338	Світильник трековий Vasmar	шт	9	
339	Шинопровід Vasmar	м	8	
340	Монтаж люстри	шт	3	
341	Люстра Leon-3	шт	3	
342	Установлення вимикачів та перемикачів пакетних 2-х і 3-х полюсних на струм до 25 А	шт	2	
343	Авт. выкл. ВА47-29 1P 10A 4,5кА х-ка С ИЕК	шт	1	
344	Авт. выкл. ВА47-29 1P 16A 4,5кА х-ка С ИЕК	шт	1	
345	Монтаж лайтбокса	шт	1	
346	Лайтбокс	шт	1	
347	Установлення блоків з кількістю установлюваних апаратів [вимикачів і штепсельних розеток] до 3	шт	5	
348	Розетка подвійна з/з	шт	5	
349	Коробка установча під бетон (100 шт)	шт	5	
350	Дюбелі 6х40	шт	10	
351	Установлення вимикачів утопленого типу при схованій проводці, 1-клавішних	шт	1	
352	Вимикач 1-кл Asfora білий	шт	1	
353	Коробка установча під бетон (100 шт)	шт	1	
354	Дюбелі 6х40	шт	2	
355	Установлення вимикачів утопленого типу при схованій проводці, 2-клавішних	шт	1	
356	Вимикач 2-кл Asfora білий	шт	1	
357	Коробка установча під бетон (100 шт)	шт	1	
358	Дюбелі 6х40	шт	2	
359	Влаштування штроб в цегляній стіні	м	6	
360	Прокладання проводів при схованій проводці в борознах	м	6	
361	ВВГ нг-LS-П 3х2,5 (5кл) (КУ) СІРИЙ	м	6,12	
362	Монтаж вініпластових труб для електропроводки діаметром до 25 мм	м	65	
363	1420 D K50D Труба гнучка с протяжкой 320 N (50м)	м	65,65	
364	Затягування першого проводу перерізом понад 2,5 мм2 до 6 мм2 в труби	м	65	
365	ВВГ нг-LS-П 3х1,5 (5кл) (КУ) СІРИЙ	м	35,7	
366	ВВГ нг-LS-П 3х2,5 (5кл) (КУ) СІРИЙ	м	30,6	
367	Заробка штробы шириною 2см, глибиною не більше 45мм	м	6	
368	Штукатурка цементна Ceresit	кг	0,6	
369	Свердління отворів в цегляних стінах, товщина стін 0,5 цеглини, діаметр отвору до 20 мм	шт	7	
370	На кожні 10 мм діаметру отворів понад 20 мм додавати	шт	7	
	<u>Розділ 8. Інше</u>	-	-	-
-	-	-	-	-
371	Обклеювання плоских поверхонь протиударною плівкою	м2	2,55	

372	Плівка протиударна	м2	2,6	
1	2	3	4	5
373	Демонтаж радіаторів масою до 80 кг	шт	2	
374	Установлення опалювальних радіаторів сталевих	кВт	4,04	
375	Настінне кріплення для радіаторів	шт	2	
376	Опалювальний прилад біметалевий секційний 10 секц.	шт	2	
377	Установлення кранів діаметром до 25 мм	шт	6	
378	Кран шар. ЗР 1/2"	шт	4	
379	Кран маєвського	шт	2	
380	Розбирання сталевих повітроводів	м2	14,2	
381	Фарбування олійними сумішами за 2 рази раніше пофарбованих сталевих труб	м2	1,3	
382	Очищення приміщень від сміття	т	1	
383	Навантаження сміття вручну	т	1	
384	Перевезення сміття до 30 км	т	1	

Technical task

No. s/n	Name of works and costs	Unit of measurement	Number	Note
1	2	3	4	5
	<u>Local estimate 02-01-01 for Premises No. 2</u>	-	-	-
-	-	-	-	-
-	<u>Section 1. Slots</u>	-	-	-
-	-	-	-	-
1	Dismantling door frames in stone walls with plaster peeling off in the slopes	pcs	1	
2	Removing door panels	m2	1.95	
3	Removing trims	m	10.2	
4	Filling doorways with ready-made door blocks with an area of more than 2 to 3 m2 made of metal-plastic in stone walls	m2	2.01	
5	Metal-plastic door blocks with glass (graphite color)	m2	2.01	
6	Ceresit mounting foam	pcs	0.5	
7	Anchor 150mm	pcs	7	
8	Installation and fastening of platbands	m	5.3	
9	Side panels (graphite color)	m	5,936	
10	Faiger Liquid Nails 280 ml Transparent	pcs	1	
11	Installing the tensioner	pcs	1	
12	Tightener (graphite color)	pcs	1	
	<u>Section 2. Ceiling</u>	-	-	-
-	-	-	-	-
13	Installation of the frame of suspended ceilings	m2	17.5	
14	Cross profile (guide) 3.6 m Armstrong	m	16.63	The volume in the DC was given by the arithmetic expression $r^2(0.95 \times 34.6)$.

15	Armstrong suspended ceiling profile 1.2 m	m	33.25	The volume in the DC was given by the arithmetic expression $r2(1.9 \times 34.6)$.
16	Armstrong suspended ceiling profile 0.6 m	m	16.63	The volume in the DC was given by the arithmetic expression $r2(0.95 \times 34.6)$.
17	Corner wall profile	m	18.9	The volume in the DC was given by the arithmetic expression $r2(1.08 \times 34.6)$.
1	2	3	4	5
18	Ceiling suspension assembly	pcs	14	The volume in the DC was given by the arithmetic expression $r0(0.8 \times 34.6)$.
19	Suspension thrust	pcs	14	The volume in the DC was given by the arithmetic expression $r0(0.8 \times 34.6)$.
20	Dowel 6/40	pcs	52	
21	Installing ceiling tiles into the Armstrong ceiling frame	m2	16.78	
22	Armstrong suspended ceiling plate	m2	17,619	The volume in the DC was given by the arithmetic expression 34.6×1.02 .
<u>Section 3. Walls</u>				
-	-	-	-	-
23	Installing a metal mesh base for plaster on brick and concrete surfaces	m2	45.6	
24	Metal mesh 15x20	m2	50.16	
25	Repair of plaster on interior walls on stone and concrete with cement mixture	m2	45.6	
26	Ceresit cement plaster	kg	775.2	
27	Facing wall surfaces with ceramic tiles on a dry adhesive mortar	m2	29.6	
28	Wall tiles	m2	29.9	
29	Primer Concrete contact	l	10.36	
30	Tile adhesive Ceresit CM 11	kg	115.44	
31	Tile crosses	pcs	304	
32	Ceresit CE 33 grout	kg	14.68	
33	Puttying walls with mineral putty	m2	16	
34	Primer Ceresit ST-17	l	3.2	
35	Start putty Knauf	kg	28.8	
36	Add 1 mm of putty thickness changes to standards 15-182-1, 15-182-2	m2	16	

37	Knauf putty Great Finish	kg	28.8	
38	Improved painting of walls with polyvinyl acetate water-based emulsion mixtures over plaster	m2	16	
39	Svart latex paint for walls and ceilings	l	10.08	
	<u>Section 4. Floors</u>	-	-	-
-	-	-	-	-
40	Dismantling wooden baseboards	m	15.9	
41	Dismantling linoleum and relin flooring	m2	17.8	
42	Installation of a 20 mm thick cement screed on a concrete base with an area of up to 20 m2 (60 mm)	m2	17.8	
43	For every 5 mm change in the thickness of the cement screed layer, add or exclude	m2	17.8	
44	Siltek F-20 mixture	kg	2136	
45	Arrangement of ceramic tile coverings on a dry adhesive mortar, the number of tiles per 1 m2 is up to 7 pieces	m2	17.8	
46	Cersanit Floyd Light tile Gray Mat Rectification	m2	18,19	
47	Primer Concrete contact	l	6.23	
48	Tile adhesive Ceresit CM 11	kg	115.7	
49	Tile crosses	pcs	75	
50	Ceresit CE 33 grout	kg	7.23	
	<u>Section 5. Window sill decoration</u>	-	-	-
-	-	-	-	-
51	Manual cleaning of window sills from oil and perchlorovinyl paint	m2	0.85	
1	2	3	4	5
52	Priming surfaces	m2	0.85	
53	Primer paint Ceresit CT 16	l	0.43	
54	Gluing surfaces with fiberglass mesh	m2	0.85	
55	mesh CCA-160 5x5 160 g/ sq.m	m2	0.89	
56	Knauf plaster Rothband	kg	3.61	
57	Continuous leveling of concrete surfaces [single-layer plastering], layer thickness 10 mm	m2	0.85	
58	Cement plaster Ceresit ST 24	kg	10.2	
59	Puttying the window sill with mineral putty	m2	0.85	
60	Primer Ceresit ST-17	l	0.17	
61	Start putty Knauf	kg	1.53	
62	Add 1 mm of putty thickness changes to standards 15-182-1, 15-182-2	m2	0.85	
63	Knauf putty Great Finish	kg	1.53	
64	Simple enamel painting of window sills on plaster and prefabricated structures	m2	0.85	
	<u>Section 6. Electrical installation work</u>	-	-	-
-	-	-	-	-
65	Dismantling of lamps	pcs	2	
66	Dismantling of switches and sockets	pcs	3	
67	Installation of fixtures for fluorescent lamps installed in suspended ceilings, number of lamps 1 pc.	pcs	2	
68	Lamp for suspended ceiling 600x600	pcs	2	
69	Installation of blocks with the number of installed devices [switches and sockets] up to 3	pcs	2	
70	Double socket with/without	pcs	2	

71	Installation box for concrete (100 pcs .)	pcs	2	
72	Dowels 6x40	pcs	4	
73	Installation of recessed switches with concealed wiring, 1-button	pcs	1	
74	Switch 1-gang Asfora white	pcs	1	
75	Installation box for concrete (100 pcs .)	pcs	1	
76	Dowels 6x40	pcs	2	
77	Installing a gate in a brick wall	m	5	
78	Laying wires with hidden wiring in grooves	m	5	
79	VVG ng -LS-P 3x1.5 (5kl) (KU) GRAY	m	2.04	
80	VVG ng -LS-P 3x2.5 (5kl) (KU) GRAY	m	3.06	
81	Installation of vinyl plastic pipes for electrical wiring with a diameter of up to 25 mm	m	10	
82	1420 D K50D Flexible pipe with extension 320 N (50m)	m	10.1	
83	Tightening the first wire with a cross section of more than 2.5 mm2	m	10	
84	VVG ng -LS-P 3x1.5 (5kl) (KU) GRAY	m	5.1	
85	VVG ng -LS-P 3x2.5 (5kl) (KU) GRAY	m	5.1	
86	Salary 2cm wide , no more than 45mm deep	m	5	
87	Ceresit cement plaster	kg	0.5	
88	Drilling holes in brick walls, wall thickness 0.5 brick, hole diameter up to 20 mm	pcs	3	
89	For every 10 mm of hole diameter over 20 mm, add	pcs	3	
	<u>Section 7. Plumbing work</u>	-	-	-
-	-	-	-	-
90	Dismantling of radiators weighing up to 80 kg	pcs	4	
91	Installation of steel heating radiators	kW	0.808	
92	Bimetallic sectional heating device DIVA 96/500 BI 4 sections.	pcs	1	
93	Wall mount for radiators	pcs	1	
94	Laying pipelines from polyethylene [polypropylene] pressure pipes with a diameter of 20 mm	m	1	
1	2	3	4	5
95	Pipes KAN -therm PP stabial PPR SDR6 (PN20) 20x2.8 20x2.8 PP STABIAL PPR	m	1	
96	Connecting new pipeline sections to existing water supply or heating networks with a diameter of 15 mm	pcs	2	
97	Thread 1/2"	pcs	2	
98	Coupling RV 20x1/2	pcs	4	
99	Installation of taps with a diameter of up to 25 mm	pcs	3	
100	Ball valve. ZR 1/2"	pcs	2	
101	Mayevsky's crane	pcs	1	
	<u>Section 8. Other</u>	-	-	-
-	-	-	-	-
102	Pasting flat surfaces with shockproof film	m2	2.55	
103	Shockproof film	m2	2.6	
104	Dismantling of steel ducts	m2	6.3	
105	Laying of air ducts with a perimeter of 1100 mm to 1600 mm made of sheet steel of class H [normal] with a thickness of 0.7 mm	m2	3.5	

106	Painting with oil mixtures for 2 times previously painted steel pipes	m2	0.9	
107	Cleaning premises from garbage	t	2.08086	
108	Manual garbage loading	t	1.95754	
109	Garbage transportation up to 30 km	t	1.95754	
	<u>Local estimate 02-01-02 for Premises No. 1</u>	-	-	-
-	-	-	-	-
-	<u>Section 1. Slots</u>	-	-	-
-	-	-	-	-
110	Dismantling door frames in stone walls with plaster peeling off in the slopes	pcs	1	
111	Removing door panels	m2	2	
112	Filling doorways with ready-made door blocks with an area of more than 2 to 3 m2 made of metal-plastic in stone walls	m2	2.05	
113	Metal-plastic door blocks with glass (graphite color)	m2	2.05	
114	Ceresit mounting foam	pcs	0.5	
115	Anchor 150mm	pcs	7	
116	Installation and fastening of platbands	m	5.35	
117	Side panels (graphite color)	m	5,992	
118	Faiger Liquid Nails 280 ml Transparent	pcs	1	
119	Installing the tensioner	pcs	1	
120	Tightener (graphite color)	pcs	1	
	<u>Section 2. Window sill decoration</u>	-	-	-
-	-	-	-	-
121	Manual cleaning of window sills from oil and perchlorovinyl paint	m2	0.85	
122	Priming surfaces	m2	0.85	
123	Primer paint Ceresit CT 16	l	0.43	
124	Gluing surfaces with fiberglass mesh	m2	0.85	
125	mesh CCA-160 5x5 160 g/ sq.m	m2	0.89	
126	Knauf plaster Rothband	kg	3.61	
127	Continuous leveling of concrete surfaces [single-layer plastering], layer thickness 10 mm	m2	0.85	
128	Cement plaster Ceresit ST 24	kg	10.2	
129	Puttying the window sill with mineral putty	m2	0.85	
130	Primer Ceresit ST-17	l	0.17	
131	Start putty Knauf	kg	1.53	
132	Add 1 mm of putty thickness changes to standards 15-182-1, 15-182-2	m2	0.85	
133	Knauf putty Great Finish	kg	1.53	
134	Simple enamel painting of window sills on plaster and prefabricated structures	m2	0.85	
1	2	3	4	5
	<u>Section 3. Ceiling</u>	-	-	-
-	-	-	-	-
135	Installation of the frame of suspended ceilings	m2	14.8	
136	Cross profile (guide) 3.6 m Armstrong	m	14.06	The volume in the DC was given by the arithmetic expression $r2(0.95 \times 34.6)$.

137	Armstrong suspended ceiling profile 1.2 m	m	28.12	The volume in the DC was given by the arithmetic expression $r^2(1.9 \times 34.6)$. The volume in the DC was given by the arithmetic expression $r^2(0.95 \times 34.6)$. The volume in the DC was given by the arithmetic expression $r^2(1.08 \times 34.6)$. The volume in the DC was given by the arithmetic expression $r^0(0.8 \times 34.6)$. The volume in the DC was given by the arithmetic expression $r^0(0.8 \times 34.6)$.
138	Armstrong suspended ceiling profile 0.6 m	m	14.06	
139	Corner wall profile	m	15.98	
140	Ceiling suspension assembly	pcs	12	
141	Suspension thrust	pcs	12	
142	Dowel 6/40	pcs	44	The volume in the DC was given by the arithmetic expression 34.6×1.02 .
143	Installing ceiling tiles into the Armstrong ceiling frame	m ²	14.08	
144	Armstrong suspended ceiling plate	m ²	14,784	
<u>Section 4. Walls</u>		-	-	-
-	-	-	-	-
145	Priming surfaces	m ²	46.2	
146	Primer paint Ceresit CT 16	l	23.1	
147	Repair of plaster on interior walls on stone and concrete with cement mixture	m ²	13.9	
148	Ceresit cement plaster	kg	236.3	
149	Continuous leveling of plaster walls inside the building with a layer thickness of up to 10 mm	m ²	27.2	
150	Cement plaster Ceresit ST 24	kg	326.4	
151	Gluingsurfaces with fiberglass mesh	m ²	46.2	
152	mesh CCA-160 5x5 160 g/ sq.m	m ²	48.51	
153	Knauf plaster Rothband	kg	196.35	
154	Installation of perforated plaster corners	m	8.9	
155	Puttying walls and boxes with mineral putty	m ²	46.2	
156	Primer Ceresit ST-17	l	9.24	
157	Start putty Knauf	kg	83.16	
158	Add 1 mm of putty thickness changes to standards 15-182-1 , 15-182-2	m ²	46.2	
159	Knauf putty Great Finish	kg	83.16	
1	2	3	4	5

160	Improved painting of walls and boxes with polyvinyl acetate water-based emulsion mixtures after plastering	m2	46.2	
161	Svart latex paint for walls and ceilings	l	29.11	
	<u>Section 5. Floors</u>	-	-	-
-	-	-	-	-
162	Dismantling wooden baseboards	m	13.4	
163	Dismantling linoleum and relin flooring	m2	15	
164	Dismantling of floor coverings made of polyvinyl chloride tiles	m2	15	
165	Dismantling of resinous floor coverings	m2	15	
166	Priming surfaces	m2	15	
167	Primer Concrete contact	l	5.25	
168	Installation of a 20 mm thick cement screed on a concrete base with an area of up to 20 m2 (80 mm)	m2	15	
169	For every 5 mm change in the thickness of the cement screed layer, add or exclude	m2	15	
170	Siltek F-20 mixture	kg	2400	
171	Arrangement of ceramic tile coverings on a dry adhesive mortar, the number of tiles per 1 m2 is up to 7 pieces	m2	15	
172	Cersanit Floyd Light tile Gray Mat Rectification	m2	15.3	
173	Primer Concrete contact	l	5.25	
174	Tile adhesive Ceresit CM 11	kg	97.5	
175	Tile crosses	pcs	64	
176	Ceresit CE 33 grout	kg	6.09	
	<u>Section 6. Electrical installation work</u>	-	-	-
-	-	-	-	-
177	Dismantling of lamps	pcs	2	
178	Dismantling of switches and sockets	pcs	2	
179	Installation of fixtures for fluorescent lamps installed in suspended ceilings, number of lamps 1 pc.	pcs	2	
180	Lamp for suspended ceiling 600x600	pcs	2	
181	Installation of blocks with the number of installed devices [switches and sockets] up to 3	pcs	1	
182	Double socket with/without	pcs	1	
183	Installation box for concrete (100 pcs .)	pcs	1	
184	Dowels 6x40	pcs	2	
185	Installation of recessed switches with concealed wiring, 1-button	pcs	1	
186	1-gang switch Asfora white	pcs	1	
187	Installation box for concrete (100 pcs .)	pcs	1	
188	Dowels 6x40	pcs	2	
189	Installing a gate in a brick wall	m	4	
190	Laying wires with hidden wiring in grooves	m	4	
191	VVG ng -LS-P 3x1.5 (5kl) (KU) GRAY	m	2.04	
192	VVG ng -LS-P 3x2.5 (5kl) (KU) GRAY	m	2.04	
193	Installation of vinyl plastic pipes for electrical wiring with a diameter of up to 25 mm	m	15	
194	1420 D K50D Flexible pipe with extension 320 N (50m)	m	15.15	
195	Tightening the first wire with a cross section of more than 2.5 mm2 to 6 mm2 into the pipes	m	15	

196	VVG ng -LS-P 3x1.5 (5kl) (KU) GRAY	m	10.2	
197	VVG ng -LS-P 3x2.5 (5kl) (KU) GRAY	m	5.1	
198	Salary 2cm wide , no more than 45mm deep	m	4	
199	Ceresit cement plaster	kg	0.4	
200	Drilling holes in brick walls, wall thickness 0.5 brick, hole diameter up to 20 mm	pcs	2	
201	For every 10 mm of hole diameter over 20 mm, add	pcs	2	
	<u>Section 7. Plumbing work</u>	-	-	-
-	-	-	-	-
1	2	3	4	5
202	(Dismantling) Installing pedestals	pcs	1	
203	Dismantling of sinks [washbasins]	kit	1	
204	Dismantling of mixers	pcs	1	
205	(Dismantling) Laying of water supply pipeline from galvanized steel water and gas pipes with a diameter of 20 mm	m	3	
206	Dismantling of pipelines made of cast iron sewer pipes with a diameter of up to 50 mm	m	0.6	
207	(Dismantling) Laying of sewage pipelines from polyethylene pipes with a diameter of 50 mm	m	1	
208	Laying pipelines from polyethylene [polypropylene] pressure pipes with a diameter of 20 mm	m	1.5	
209	Pipes KAN -therm PP stabial PPR SDR6 (PN20) 20x2.8 20x2.8 PP STABIAL PPR	m	1.5	
210	Adapter (reduction) d.20	pcs	1	
211	Pipe fittings d.20	pcs	3	
212	Installation of single washbasins with cold water supply	kit	1	
213	Washbasin with bedside table	pcs	1	
214	Siphon for washbasin	pcs	1	
215	Flexible hose	pcs	1	
216	Installing faucets	pcs	1	
217	Mixers	pcs	1	
218	Installation of water-distributing coupling valves	pcs	1	
219	Ball valve. ZR 1/2"	pcs	1	
220	Installation of steel plugs on pipelines with a diameter of up to 100 mm	stub	2	
221	1/2" plug	pcs	2	
222	Installation of inspection hatch	pcs	1	
223	Inspection hatch 200*200	pcs	1	
224	Connecting new pipeline sections to existing water supply or heating networks with a diameter of 15 mm	pcs	1	
225	Thread 1/2"	pcs	1	
226	Coupling RV 20x1/2	pcs	2	
227	Punching grooves in brick walls	m	2.7	
228	Salary stobes	m	2.7	
229	Ceresit cement plaster	kg	2.7	
230	Drilling holes in brick walls	pcs	3	
	<u>Section 8. Other</u>	-	-	-
-	-	-	-	-
231	Pasting flat surfaces with shockproof film	m2	2.55	

232	Shockproof film	m2	2.6	
233	Painting with oil mixtures twice over previously painted radiators and finned tubes	m2	3.33	
234	Painting with oil mixtures for 2 times previously painted steel pipes	m2	0.14	
235	Cleaning premises from garbage	t	1.29283	
236	Manual garbage loading	t	1.76951	
237	Garbage transportation up to 30 km	t	1.76951	
	<u>Local estimate 02-01-03 for Room No. 5</u>	-	-	-
-	-	-	-	-
-	<u>Section 1. Slots</u>	-	-	-
-	-	-	-	-
238	Dismantling door frames in stone walls with plaster peeling off in the slopes	pcs	1	
239	Removing door panels	m2	2	
240	Filling doorways with ready-made door blocks with an area of more than 2 to 3 m2 made of metal-plastic in stone walls	m2	2.05	
241	Metal-plastic door blocks with glass (graphite color)	m2	2.05	
1	2	3	4	5
242	Ceresit mounting foam	pcs	0.5	
243	Anchor 150mm	pcs	7	
244	Installation and fastening of platbands	m	5.4	
245	Side panels (graphite color)	m	6,048	
246	Faiger Liquid Nails 280 ml Transparent	pcs	1	
247	Installing the tensioner	pcs	1	
248	Tightener (graphite color)	pcs	1	
	<u>Section 2. Ceiling</u>	-	-	-
-	-	-	-	-
249	(Dismantling) Pasting of stretch ceiling material	m2	28	
250	(Dismantling) Installation of steel profiles	m	21.2	
251	(Dismantling) of wooden bar ceiling structures	m2	35.25	
252	Dismantling of suspended ceilings made of asbestos cement boards	m2	35.25	
253	Dismantling baguettes	m	21.3	
254	Dismantling the plasterboard box lining	m2	14.2	
255	Dismantling the box frame	m2	14.2	
256	Installation of the frame of suspended ceilings	m2	35.25	
257	Laying ceiling tiles " Grylyato" in the ceiling frame	m2	35.25	
258	Grilyato profile upper	pcs	487	
259	Grilyato lower profile	pcs	487	
260	Anchor wedge 60*40	pcs	74	
261	Ceiling suspension assembly	pcs	74	The volume in the DC was given by the arithmetic expression $r_0(0.8 \times 34.6)$. The volume in the DC was given by the arithmetic expression $r_0(0.8 \times 34.6)$.
262	Suspension thrust	pcs	74	

263	Dowel 6x60	pcs	105	
264	Connector for Grilyato	pcs	23	
265	Grilyato profile 0.6m	pcs	98	
266	Wall profile 2m	pcs	12	
267	Grilyato profile 2.4m	pcs	25	
268	Coating and filling the seams of the ceiling panels with mortar from below	m seam	35.4	
269	Priming surfaces	m2	50.3	
270	Primer Ceresit ST-17	l	10.06	
271	Improved black ceiling painting	m2	50.3	
272	Svart latex paint for walls and ceilings	l	34.71	
	<u>Section 3. Floor</u>			
-	-	-	-	-
273	Dismantling wooden baseboards	m	21.3	
274	Surface finishing of parquet flooring that has been in use	m2	36.8	
275	Tikkurila putty	l	5.89	
276	Tikkurila varnish	l	15.46	
277	Primer Tikkurila	l	9.2	
278	Installation of wooden skirting boards with screw fastening	m	21.3	
279	Floor skirting board	m	21,513	
280	Dowel 6x60	pcs	32	
	<u>Section 4. Walls</u>			
-	-	-	-	-
281	Simple and advanced wallpaper removal	m2	27.4	
282	limestone wall cladding	m2	2	
1	2	3	4	5
283	Facing of wall surfaces with tiles on a dry adhesive mortar, the number of tiles per 1 m2 up to 7 pieces (previously dismantled)	m2	2	
284	Primer Concrete contact	l	0.7	
285	Tile adhesive Ceresit CM 11	kg	13	
286	Tile crosses	pcs	8	
287	Ceresit CE 33 grout	kg	0.81	
288	Priming surfaces	m2	25.7	
289	Primer Ceresit ST-17	l	5.14	
290	Painting tiles	m2	25.7	
291	Svart latex paint for walls and ceilings	l	16.19	
292	Priming surfaces	m2	43.1	
293	Primer Ceresit ST-17	l	8.62	
294	Repair of plaster on interior walls on stone and concrete with cement mixture	m2	13	
295	Ceresit cement plaster	kg	221	
296	Continuous leveling of plaster walls inside the building with a thickness of up to 10 mm	m2	30.1	
297	Cement plaster Ceresit ST 24	kg	361.2	
298	Gluingsurfaces with fiberglass mesh	m2	43.1	
299	mesh CCA-160 5x5 160 g/ sq.m	m2	45.26	
300	Knauf plaster Rothband	kg	183.18	
301	Installation of perforated plaster corners	m	10.4	
302	Puttying walls with mineral putty	m2	43.1	

303	Primer Ceresit ST-17	l	8.62	
304	Start putty Knauf	kg	77.58	
305	Add 1 mm of putty thickness changes to standards 15-182-1 , 15-182-2	m2	43.1	
306	Knauf putty Great Finish	kg	77.58	
307	Improved painting of walls and boxes with polyvinyl acetate water-based emulsion mixtures after plastering	m2	43.1	
308	Svart latex paint for walls and ceilings	l	27.15	
	<u>Section 5. Window sill decoration</u>	-	-	-
309	Manual cleaning of window sills from oil and perchlorovinyl paint	m2	1.7	
310	Priming surfaces	m2	1.7	
311	Primer paint Ceresit CT 16	l	0.85	
312	Gluing surfaces with fiberglass mesh	m2	1.7	
313	mesh CCA-160 5x5 160 g/ sq.m	m2	1.79	
314	Knauf plaster Rothband	kg	7.23	
315	Continuous leveling of concrete surfaces [single-layer plastering], layer thickness 10 mm	m2	1.7	
316	Cement plaster Ceresit ST 24	kg	20.4	
317	Puttying the window sill with mineral putty	m2	1.7	
318	Primer Ceresit ST-17	l	0.34	
319	Start putty Knauf	kg	3.06	
320	Add 1 mm of putty thickness changes to standards 15-182-1 , 15-182-2	m2	1.7	
321	Knauf putty Great Finish	kg	3.06	
322	Simple enamel painting of window sills on plaster and prefabricated structures	m2	1.7	
	<u>Section 6. Slopes</u>	-	-	-
323	Plastering	m2	4.35	
324	Arrangement of slopes sheathing with plasterboard and gypsum fiber sheets with adhesive fastening	m2	4.35	
325	Knauf moisture-resistant drywall	m2	4.5675	
326	Perforated corners	m	16	
1	2	3	4	5
327	Glue for plasterboard Knauf PERLFIX	kg	21.75	
328	Puttying slopes with mineral putty	m2	4.35	
329	Primer Ceresit ST-17	l	0.87	
330	Add 1 mm of putty thickness changes to standards 15-182-1 , 15-182-2	m2	4.35	
331	Knauf putty Great Finish	kg	15.66	
332	Improved painting of slopes on plaster with polyvinyl acetate water-based emulsion mixtures	m2	4.35	
333	Svart latex paint for walls and ceilings	l	2.74	
	<u>Section 7. Electrical installation work</u>	-	-	-
334	Dismantling of switches and sockets	pcs	4	
335	Dismantling of LED lamps	pcs	4	

336	(Dismantling) Chandelier installation	pcs	1	
337	Track installation	pcs	9	
338	Vasmar track lamp	pcs	9	
339	Busbar Vasmar	m	8	
340	Chandelier installation	pcs	3	
341	Chandelier Leon-3	pcs	3	
342	Installation of 2- and 3-pole package switches and switches for current up to 25 A	pcs	2	
343	Auth . off BA47-29 1P 10A 4.5kA x-ka C IEK	pcs	1	
344	Auth . off BA47-29 1P 16A 4.5kA x-ka C IEK	pcs	1	
345	Lightbox installation	pcs	1	
346	Lightbox	pcs	1	
347	Installation of blocks with the number of installed devices [switches and sockets] up to 3	pcs	5	
348	Double socket with/without	pcs	5	
349	Installation box for concrete (100 pcs .)	pcs	5	
350	Dowels 6x40	pcs	10	
351	Installation of recessed switches with concealed wiring, 1-button	pcs	1	
352	1-gang switch Asfora white	pcs	1	
353	Installation box for concrete (100 pcs .)	pcs	1	
354	Dowels 6x40	pcs	2	
355	Installation of recessed switches with concealed wiring, 2-button	pcs	1	
356	2-gang switch Asfora white	pcs	1	
357	Installation box for concrete (100 pcs .)	pcs	1	
358	Dowels 6x40	pcs	2	
359	Installing a gate in a brick wall	m	6	
360	Laying wires with hidden wiring in grooves	m	6	
361	VVG ng -LS-P 3x2.5 (5kl) (KU) GRAY	m	6.12	
362	Installation of vinyl plastic pipes for electrical wiring with a diameter of up to 25 mm	m	65	
363	1420 D K50D Flexible pipe with extension 320 N (50m)	m	65.65	
364	Tightening the first wire with a cross section of more than 2.5 mm ² to 6 mm ² into the pipes	m	65	
365	VVG ng -LS-P 3x1.5 (5kl) (KU) GRAY	m	35.7	
366	VVG ng -LS-P 3x2.5 (5kl) (KU) GRAY	m	30.6	
367	Salary 2cm wide , no more than 45mm deep	m	6	
368	Ceresit cement plaster	kg	0.6	
369	Drilling holes in brick walls, wall thickness 0.5 brick, hole diameter up to 20 mm	pcs	7	
370	For every 10 mm of hole diameter over 20 mm, add	pcs	7	
	<u>Section 8. Other</u>	-	-	-
		-	-	-
371	Pasting flat surfaces with shockproof film	m ²	2.55	
372	Shockproof film	m ²	2.6	
1	2	3	4	5
373	Dismantling of radiators weighing up to 80 kg	pcs	2	
374	Installation of steel heating radiators	kW	4.04	
375	Wall mount for radiators	pcs	2	

376	Bimetallic sectional heating device, 10 sections .	pcs	2	
377	Installation of taps with a diameter of up to 25 mm	pcs	6	
378	Ball valve. ZR 1/2"	pcs	4	
379	Mayevsky's crane	pcs	2	
380	Dismantling of steel ducts	m2	14.2	
381	Painting with oil mixtures for 2 times previously painted steel pipes	m2	1.3	
382	Cleaning premises from garbage	t	1	
383	Manual garbage loading	t	1	
384	Garbage transportation up to 30 km	t	1	

**Лист-відповідь
на запит цінових пропозицій**

**щодо закупівлі послуги з поточного ремонту дегустаційної зали та службових приміщень
профорієнтаційного хабу у Комунальному закладі “Чернігівський центр
професійно-технічної освіти” Чернігівської обласної ради в межах напрямку “Підтримка
реформи професійної освіти в Україні” Швейцарсько-українського Проєкту DECIDE**

Дата _____
Місце _____

Назва подавача цінової пропозиції _____
Юридична адреса _____
Контактна інформація _____

У відповідь на запит надаємо цінову пропозицію відповідно до технічного завдання:

№ п/п	Найменування робіт та витрат	Одиниця виміру	Кількість	Вартість в грн. (UAH), без ПДВ

ПІБ:
Підпис:
Печатка за наявності

**Answer letter
to the request for quotation**

**regarding the procurement of services for the current repair of the tasting room and staff premises
of the Career Guidance Hub at the Municipal Institution “Chernihiv Center for Vocational
Education” of the Chernihiv Regional Council within the framework of the initiative
“Support to the reform of vocational education in Ukraine” direction of the Swiss-Ukrainian
DECIDE Project**

Date _____
Place _____

The name of the bidder _____

Legal address _____

Contact information _____

In response to the request, we provide a price offer in accordance with the technical task:

№	Name of works and costs	Unit of measurement	Number	Price in UAH (UAH), excluding VAT

Full name:

Signature:

Stamp

Компанія:

Дата:

Лист-повідомлення

Шановні панове, дякуємо за Ваше зацікавлення у наших послугах. На Ваш запит доводимо до Вашого відома наступне:

- 1) _____ зареєстрований згідно чинного законодавства на території України.
- 2) _____ не є банкрутом, проти нас не розпочата процедура банкрутства, не розглядаються судові позови, всі зобов'язання перед кредиторами є виконаними, ми не припиняємо ділову активність та надання товарів/послуг;
- 3) Ми не були обвинувачені у будь-якому злочині, що стосується нашої професійної діяльності, та не підлягаємо будь-якому покаранню за судовим вироком, який не підлягає оскарженню;
- 4) Ми не є об'єктом судового рішення, яке має законну силу за звинуваченням у шахрайстві, корупції, участі у злочинній організації або будь-який інший незаконній діяльності.
- 5) Всі зобов'язання, пов'язані з сплатою внесків на соціальне страхування та сплатою податків у відповідності з правовими нормами країни, де ми зареєстровані, або країни, де виконуватимуться умови контракту є виконаними.

(Підпис) _____

Company:

Date:

Letter of notification

Dear Sirs, Thank you for your interest in our services. At your request, we bring the following to your attention:

- 1) _____ registered in accordance with the current legislation on the territory of Ukraine.
- 2) _____ is not bankrupt, no bankruptcy proceedings have been initiated against us, no lawsuits are pending, all obligations to creditors have been fulfilled, we do not stop business activity and the provision of goods/services;
- 3) We have not been charged with any crime related to our professional activities and are not subject to any punishment by a court judgment that is not subject to appeal;
- 4) We are not the subject of a valid court decision on charges of fraud, corruption, participation in a criminal organization or any other illegal activity.
- 5) All obligations related to the payment of social insurance contributions and the payment of taxes in accordance with the legal regulations of the country where we are registered or the country where the terms of the contract will be fulfilled are fulfilled.

(Signature) _____