



Republic of the Philippines

Department of Health

Central Visayas Center for Health Development

DON EMILIO DEL VALLE MEMORIAL HOSPITAL

PHILHEALTH ACCREDITED HEALTHCARE PROVIDER

ISO 9001:2015 QMS CERTIFIED

## Bid Form for the Procurement of Infrastructure Projects

*[shall be submitted with the Bid]*

### BID FORM

#### Repair/ Renovation of Ground Floor of Dona Felomina Building

Date : \_\_\_\_\_  
Project Identification No. \_\_\_\_\_

To: *[name and address of Procuring Entity]*

Having examined the Philippine Bidding Documents (PBDs) including the Supplemental or Bid Bulletin Numbers *[insert numbers]*, the receipt of which is hereby duly acknowledged, we, the undersigned, declare that:

Description of Requirement/ Project	Approved Budget for the Contract (ABC), inclusive of all applicable taxes and other charges	Total Bid Price, inclusive of all applicable taxes and other charges
Repair/ Renovation of Ground Floor of Dona Felomina Building	Php 10,000,000.00  Any bid with financial proposal exceeding the amount shall not be accepted	

- We have no reservation to the PBDs, including the Supplemental or Bid Bulletins, for the Procurement Project: *[insert name of contract]*;
- We offer to execute the Works for this Contract in accordance with the PBDs;
- The total price of our Bid in words and figures, excluding any discounts offered below is: *[insert information]*;
- The discounts offered and the methodology for their application are: *[insert information]*;
- The total bid price includes the cost of all taxes, such as, but not limited to: *[specify the applicable taxes, e.g. (i) value added tax (VAT), (ii) income tax, (iii) local taxes, and (iv) other fiscal levies and duties]*, which are itemized herein and reflected in the detailed estimates,

Printed Name and Signature of Proprietor/Manager/Authorized Representative

- f. Our Bid shall be valid within the a period stated in the PBDs, and it shall remain binding upon us at any time before the expiration of that period;
- g. If our Bid is accepted, we commit to obtain a Performance Security in the amount of *[insert percentage amount]* percent of the Contract Price for the due performance of the Contract, or a Performance Securing Declaration in lieu of the the allowable forms of Performance Security, subject to the terms and conditions of issued GPPB guidelines<sup>1</sup> for this purpose;
- h. We are not participating, as Bidders, in more than one Bid in this bidding process, other than alternative offers in accordance with the Bidding Documents;
- i. We understand that this Bid, together with your written acceptance thereof included in your notification of award, shall constitute a binding contract between us, until a formal Contract is prepared and executed; and
- j. We understand that you are not bound to accept the Lowest Calculated Bid or any other Bid that you may receive.
- k. We likewise certify/confirm that the undersigned, is the duly authorized representative of the bidder, and granted full power and authority to do, execute and perform any and all acts necessary to participate, submit the bid, and to sign and execute the ensuing contract for the [Name of Project] of the [Name of the Procuring Entity].
- l. We acknowledge that failure to sign each and every page of this Bid Form, including the Bill of Quantities, shall be a ground for the rejection of our bid.

Name: \_\_\_\_\_

Legal Capacity: \_\_\_\_\_

Signature: \_\_\_\_\_

Duly authorized to sign the Bid for and behalf of: \_\_\_\_\_

Date: \_\_\_\_\_

---

<sup>1</sup> currently based on GPPB Resolution No. 09-2020

Printed Name and Signature of Proprietor/Manager/Authorized Representative



Republic of the Philippines  
 Department of Health  
 Central Visayas Center for Health Development  
**DON EMILIO DEL VALLE MEMORIAL HOSPITAL**  
 PHILHEALTH ACCREDITED HEALTHCARE PROVIDER  
 ISO 9001:2015 QMS CERTIFIED

**BILL OF QUANTITIES**

Project Name/Description:		<b>Rapar/Renovation of Ground Floor of Doña Felomina Building</b>			
Project Location:		<b>DEVMH Compound, Bood, Ubay, Bohol</b>			
Duration:		_____ Calendar Days			
Item No.	Description	Qty	Unit	Adjusted Direct Unit Cost	Total Amount
A.	GENERAL REQUIREMENTS				
A.1	Mobilization/Demobilization	1.00	lot		
A.2	Permits & Licenses				
A.2.1	Electrical Review, Analysis, Computations & Signature of PEE on Electrical Plans, Inclusive sign and seal	1.00	lot/s		
A.2.2	DOH Licences (Permit to Construct - PTC)	1.00	lot		
A.3	Temporary Facilities				
A.3.1	Security, Temporary water and Power Supply, Bunk House, etc	1.00	lot/s		
A.4	Construction Safety Requirements				
A.4.1	Safety Requirements (Hard hat, shoes, safety belt, safety signages, billboards and etc.)	1.00	lot/s		
A.5	Others				
A.5.1	As-built (Softcopy - AutoCAD file & Hardcopy)	1.00	lot/s		
I.	DEMOLITION/CLEARING				
I.1	Demolition/Clearing Works for Ceiling	519.05	sqm		
I.2	Demolition/Clearing Works for Concrete walls	197.25	sqm		
I.3	Chipping of Existing Tile Setting	495.51	sqm		
II.	STRUCTURAL CONCRETE (Incl. forms & scaffoldings)				
II.1	Wall Footing, 3500 psi	8.75	cu.m.		
II.1.1	Portland Cement		bags		
II.1.2	Fine Aggregates		cu.m.		
II.1.3	Coarse Aggregates		cu.m.		
II.1.4	Deformed Bar, 10mmØ, Grade 40		lengths		
II.1.5	G.I. Tie Wire, #16		kgs.		
II.2	Concrete Countertop Sink, 3500 psi	0.70	cu.m.		
II.2.1	Portland Cement		bags		
II.2.2	Fine Aggregates		cu.m.		
II.2.3	Coarse Aggregates		cu.m.		
II.2.4	Deformed Bar, 10mmØ, Grade 40		lengths		
II.2.5	G.I. Tie Wire, #16		kgs.		
II.3	Stiffener Columns and Lintel Beams at Door and Window Openings, every 3m width and 2.1m height of CHB 2500 psi	9.61	cu.m.		
II.3.1	Portland Cement		bags		
II.3.2	Fine Aggregates		cu.m.		
II.3.3	Coarse Aggregates		cu.m.		
II.3.4	Deformed Bar, 10mmØ, Grade 60		lengths		
II.3.5	G.I. Tie Wire, #16		kgs.		
II.4	Formworks & Scaffoldings	40.61	cu.m.		
II.4.1	Concrete formworks and form accessories, braces, scaffoldings, shoring, hoist, etc.	40.61	sq.m.		
III.	MASONRY WORKS				
III.1	Interior wall: 4" thk CHB w/ 10mm dia. vert. bar @ 0.40m o.c. w/ 10mm dia. hor. bar every 2nd layer	412.27	sq.m.		
III.1.1	Portland Cement		bags		
III.1.2	Fine Aggregates		cu.m.		
III.1.3	Concrete Hollow Blocks, 4", 450 Psi		pcs		
III.1.4	Deformed Bar, 10mmØ, Grade 60		lengths		
III.1.5	G.I. Tiewire #16		kgs.		
III.2	Exterior and Interior Plastering, 25mm thk including smooth finish (for the whole area)	824.55	sq.m.		
III.2.1	Masonry Cement		bags		
III.2.2	Fine Aggregates		cu.m.		
IV.	CARPENTRY WORKS				

Printed Name and Signature of Proprietor/Manager/Authorized Representative

Printed Name and Signature of Proprietor/Manager/Authorized Representative

Item No.	Description	Qty	Unit	Adjusted Direct Unit Cost	Total Amount
IV.1	Ceiling, 4.5 mm thk. Fiber Cement Board, 4' x 8' on Light Metal Framing Spaced @ 0.40m O.C. B.W.	618.81	sq.m.		
IV.1.1	4.5 mm thk. Fiber Cement Board, 4' x 8'		pcs		
IV.1.2	Ficem Board Screw, 20mm long		pcs		
IV.1.3	Double Furring, 19mm x 50mm x 5m, t=0.40mm		lengths		
IV.1.4	Pan Head Screw, 1/2", (Metal)		pcs		
IV.1.5	Carrying Channel, 12mm x 38mm x 3m, t=0.80mm		lengths		
IV.1.6	Wall Angle, 25mm x 25mm x 3.0m, t=0.40mm		lengths		
IV.1.7	Vertical Hanger (Carrying Channel)		lengths		
IV.1.8	Double furring clip		pcs		
IV.1.9	Concrete Nails, 1"		kls		
IV.2	Ceiling Coveelight & Drop Ceiling Cladding, 4.50 mm thk. Fiber Cement Board, 4' x 8' on Light Metal Framing Spaced @ 0.40m O.C.	96.50	l.m.		
IV.2.1	4.50mm thk. Fiber Cement Board, 4' x 8'		pcs		
IV.2.2	Ficem Board Screw, 20mm long		pcs		
IV.2.3	Pan Head Screw, 1/2", (Metal)		pcs		
IV.2.4	Double Furring, 19mm x 50mm x 5m, t=0.40mm		lengths		
V.	FINISHES				
	*Note:				
V.1	Glazed Ceramic Floor Tiles 600mm x 600mm	458.00	sq.m.		
V.1.1	Non-skid, Ceramic Floor Tiles 600mm x 600mm		pcs.		
V.1.2	Tile Adhesive		bags		
V.1.3	Tile Grout, 2 kls.		packs		
V.2	Unglazed Ceramic Floor Tiles 600mm x 600mm	98.00	sq.m.		
V.2.1	Non-skid, Ceramic Floor Tiles 600mm x 600mm		pcs.		
V.2.2	Tile Adhesive		bags		
V.2.3	Tile Grout, 2 kls.		packs		
V.3	Non-skid Ceramic Wall Tiles 300mm x 300mm	13.50	sq.m.		
V.3.1	Non-skid Ceramic Wall Tiles 300mm x 300mm		pcs.		
V.3.2	Tile Adhesive		bags		
V.3.3	Tile Grout, 2 kls.		packs		
V.3.4	PVC Tile Trim, 2.4m		lengths		
V.4	Glossy/Polished, Ceramic Wall Tiles 300mm x 600mm (floor to ceiling)	77.56	sq.m.		
V.4.1	Glossy/Polished, Ceramic Wall Tiles 300mm x 600mm		pcs.		
V.4.2	Tile Adhesive		bags		
V.4.3	Tile Grout, 2 kls.		packs		
V.4.4	PVC Tile Trim, 2.4m		lengths		
V.5	Counter Sink Tiles, Glossy/Polished, Ceramic Tiles 600mm x 600mm	21.08	sq.m.		
VI.5.1	Concrete Sink Tiles, Glossy/Polished, Ceramic Tiles 600mm x 600mm		pcs.		
VI.5.2	Tile Adhesive		bags		
VI.5.3	Tile Grout, 2 kls.		packs		
VI.5.4	PVC Tile Trim, 2.4m		lengths		
V.6	Painting; Concrete Walls (Exterior)	314.32	sq.m.		
V.6.1	Semi-gloss Latex, (4L = 2 Coats)		gals		
V.6.2	Concrete neutralizer, 4L		gals		
V.6.3	Skimcoat		bags		
V.6.4	Patching Compound		kgs		
V.6.5	Primer Paint (2 Coats)		gal		
V.7	Painting; Concrete Walls including all opening's perimeter (Interior)	994.96	sq.m.		
V.7.1	Semi-gloss Latex, (4L = 2 Coats)		gals		
V.7.2	Concrete neutralizer, 4L		gals		
V.7.3	Skimcoat		bags		
V.7.4	Patching Compound		kgs		
V.7.5	Primer Paint (2 Coats)		gal		
V.8	Painting; Ceiling ( Interior ) including coveelight and drop ceilings	929.90	sq.m.		
V.8.1	White Flat Latex, 4L (2 coats)		gals		
V.8.2	Putty		gals		
V.8.3	Patching Compound		kgs		
V.8.4	Primer Paint (2 coats)		gal		
VII.	ARCHITECTURAL WORKS, SPECIALTIES & ACCESSORIES				
VII.1	Doors (Incl. Jamb, Locks, Door Closer & Accessories)	28.00	Sets		
VII.1.1	D01 (2.10m x 2.15m) 12mm thk. Tempered clear glass Frameless door with 2" x 6" powder coated aluminum jamb with complete hardware accessories	2.00	set/s		

Printed Name and Signature of Proprietor/Manager/Authorized Representative

Item No.	Description	Qty	Unit	Adjusted Direct Unit Cost	Total Amount
VII.1.2	D02 (1.50m x 2.15m) 1/4" thk. Clear Glass door on 50mm x 100mm powder-coated aluminum framed door with 2" x 6" powder coated aluminum jamb with complete hardware accessories	2.00	set/s		
VII.1.3	D03 (1.10m x 2.15m) 1/4" thk. Clear Glass door on 50mm x 100mm powder-coated aluminum framed door with 2" x 6" powder coated aluminum jamb with complete hardware accessories	2.00	set/s		
VII.1.4	D04 (1.70m x 2.10m) Hollow core metal flush type swinging door w/ 500mmx800mm view window on 6mm thk wired glass with 2" x 6" steel jamb on double action hinges and complete hardware accessories in automotive finish	3.00	set/s		
VII.1.5	D05 (1.50m x 2.10m) Hollow core metal flush type swinging door w/ 500mmx800mm view window on 6mm thk wired glass with 2" x 6" steel jamb on double action hinges and complete hardware accessories in automotive finish	1.00	set/s		
VII.1.6	D06 (1.50m x 2.10m) Hollow core metal flush type swinging door w/ 500mmx800mm view window on 6mm thk wired glass with 2" x 6" steel jamb on double action hinges and complete hardware accessories in automotive finish	3.00	set/s		
VII.1.7	D07 (1.10m x 2.10m) Solid panel door w/ 2" x 6" wood jamb already installed, provide w/ ball bearing, full mortise on heavy duty hinges and complete hardware accessories in automotive finish	2.00	set/s		
VII.1.8	D08 (0.80m x 2.10m) Solid panel door w/ 2" x 6" wood jamb already installed, provide w/ ball bearing, full mortise on heavy duty hinges and complete hardware accessories in automotive finish	8.00	set/s		
VII.1.9	D09 (0.90m x 2.10m) Solid panel door w/ 2" x 6" wood jamb already installed, provide w/ ball bearing, full mortise on heavy duty hinges and complete hardware accessories in automotive finish	4.00	set/s		
VII.1.10	D10 (0.80m x 2.10m) Double swing 1/2" Aluminum louver door panel painted finish w/ 2" x 6" steel jamb w/ double action heavy duty hinges w/ complete hardware accessories in automotive finish	1.00	set/s		
VII.2	Windows (Incl. Jamb, Locks & Accessories)	6.00	Sets		
VII.2.1	W01 - (1.80m x 1.20m) 1/4" thk clear glass sliding window powder-coated aluminum frame w/ complete hardware accessories	3.00	set/s		
VII.2.2	W02 - (1.25m x 0.60m) 1/4" thk clear glass sliding window powder-coated aluminum frame w/ complete hardware accessories	1.00	set/s		
VII.2.3	W03 - (1.60m x 1.00m) 1/4" thk clear glass fixed window on powder-coated aluminum frame w/ complete hardware accessories	1.00	set/s		
VII.2.4	W04 - (0.83m x 1.00m) 1/4" thk clear glass fixed window on powder-coated aluminum frame w/ complete hardware accessories	1.00	set/s		
VII.3	Building/Room Signages/Wayfinding Systems	32.00	Sets		
VII.3.1	Room Identification Sign - CHIEF NURSE OFFICE, 6mm thick Frosted Acrylic	4.00	set/s		
VII.3.2	Room Identification Sign - PULMONARY UNIT, 6mm thick Frosted Acrylic	1.00	set/s		
VII.3.3	Room Identification Sign - PHYSICAL THERAPIST ROOM, 6mm thick Frosted Acrylic	1.00	set/s		
VII.3.4	Room Identification Sign - JANITORS CLOSET, 6mm thick Frosted Acrylic	2.00	set/s		
VII.3.5	Room Identification Sign - ELECTRICAL ROOM, 6mm thick Frosted Acrylic	2.00	set/s		
VII.3.6	Room Identification Sign - BUSINESS OFFICE, 6mm thick Frosted Acrylic	2.00	set/s		
VII.3.7	Room Identification Sign - STAKEHOLDERS OFFICE, 6mm thick Frosted Acrylic	3.00	set/s		
VII.3.8	Room Identification Sign - TREATMENT AREA, 6mm thick Frosted Acrylic	1.00	set/s		
VII.3.9	Room Identification Sign - DOCTORS OFFICE, 6mm thick Frosted Acrylic	1.00	set/s		
VII.3.10	Room Identification Sign - PANTRY, 6mm thick Frosted Acrylic	1.00	set/s		
VII.3.11	Room Identification Sign - WATER TREATMENT ROOM, 6mm thick Frosted Acrylic	3.00	set/s		
VII.3.12	Room Identification Sign - REPROCESSING ROOM, 6mm thick Frosted Acrylic	1.00	set/s		
VII.3.13	Room Identification Sign - WASTE HOLDING AREA, 6mm thick Frosted Acrylic	2.00	set/s		
VII.3.14	Room Identification Sign - NURSE STATION, 6mm thick Frosted Acrylic	3.00	set/s		
VII.3.19	Restroom Identification - PWD Toilet, 6mm thick Frosted Acrylic	1.00	set/s		
VII.3.20	Restroom Identification - All Gender Toilet, 6mm thick Frosted Acrylic	2.00	set/s		
VII.3.21	Restroom Identification - Staff Toilet, 6mm thick Frosted Acrylic	1.00	set/s		
VII.3.22	Emergency Exit Plan, 6mm thick Frosted Acrylic	1.00	set/s		
VIII.	PLUMBING WORKS				
VIII.1	Wasteline Pipings, S1000, Fittings & Accessories	1.00	lot		
VIII.1.1	PVC Pipe 4"Ø S1000 Sanitary Pipe		length/s		
VIII.1.2	PVC Pipe 2"Ø S1000 Sanitary Pipe		length/s		

Printed Name and Signature of Proprietor/Manager/Authorized Representative

Item No.	Description	Qty	Unit	Adjusted Direct Unit Cost	Total Amount
VIII.1.3	PVC Wye Reducer 8"x4"		pc/s		
VIII.1.4	PVC Wye Reducer 4"x2"		pc/s		
VIII.1.5	PVC Wye 4"x4"		pc/s		
VIII.1.6	PVC Wye 2"x2"		pc/s		
VIII.1.7	PVC Elbow 4"x90		pc/s		
VIII.1.8	PVC Elbow 4"x45		pc/s		
VIII.1.9	PVC Elbow 2"x45		pc/s		
VIII.1.10	PVC Elbow 2"x90		pc/s		
VIII.1.11	PVC Tee 4"x4"		pc/s		
VIII.1.12	PVC Tee 4"x2"		pc/s		
VIII.1.13	PVC Tee 2"x2"		pc/s		
VIII.1.14	PVC P-Trap 4"		pc/s		
VIII.1.15	PVC P-Trap 2"		pc/s		
VIII.1.16	PVC Bottle-Trap 2"		pc/s		
VIII.1.17	PVC Coupling 4"Ø		pc/s		
VIII.1.18	PVC Coupling 2"Ø		pc/s		
VIII.1.19	PVC Clean Out 4"Ø		pc/s		
VIII.1.20	PVC Clean Out 2"Ø		pc/s		
VIII.1.21	Stainless Steel Vent Cap 4"Ø		pc/s		
VIII.1.22	Stainless Steel Vent Cap 2"Ø		pc/s		
VIII.1.23	Solvent Cement, 200cc		liter/s		
VIII.1.24	Sealant (Vulcaseal)		liter/s		
VIII.2	Waterline Piping, Fittings ^ Accessories	1.00	lot		
VIII.2.1	PPR Pipe 2"Ø		length/s		
VIII.2.2	PPR Pipe 1 1/2"Ø		length/s		
VIII.2.3	PPR Pipe 1/2"		length/s		
VIII.2.4	PPR Elbow 2" Plain		pc/s		
VIII.2.5	PPR Elbow 1 1/2" Plain		pc/s		
VIII.2.6	PPR Elbow 1/2" plain		pc/s		
VIII.2.7	PPR Tee 2"		pc/s		
VIII.2.8	PPR Tee 1 1/2"		pc/s		
VIII.2.9	PPR Tee 1/2" plain		pc/s		
VIII.2.10	PPR Coupling 1/2"		pc/s		
VIII.2.11	PPR Female Adaptor 1/2"		pc/s		
VIII.2.12	PPR Reducer 2"x 1/2"		pc/s		
VIII.2.13	PPR Reducer 1 1/2"x 1/2"		pc/s		
VIII.2.14	PPR Gate Valve 1/2"		pc/s		
VIII.2.15	Angle Valve 1/2"x1/2"		pc/s		
VIII.2.16	Flexible Hose 1/2"x1/2"x16"		pc/s		
VIII.2.17	Teflon Tape 1"		pc/s		
VIII.3	Plumbing Fixtures	1.00	lot		
	* Submit samples for approval prior to installation				
	** Faucets, valves & other accessories shall be Japan, U.S., & E.U. made				
VIII.3.1	Two-Piece Water Closet/s (push button, 4/6 liters water saver) with wall-mounted Semi-recessed Ceramic Tissue Holder, wall-mounted Semi-recessed Ceramic Soap Holder, complete accessories	7.00	set/s		
VIII.3.2	Lavatory with Pedestal w/ faucet and w/ Complete Fittings & Accessories	8.00	set/s		
VIII.3.3	600x400x200x0.8 mm Stainless Steel Single Bowl Kitchen Sink w/ Complete Fittings & Accessories	5.00	set/s		
VIII.3.4	Urinal w/ Complete Fittings & Accessories	2.00	set/s		
VIII.3.5	SS 304 Towel Bar	7.00	pc/s		
VIII.3.6	Stainless Faucet	8.00	pc/s		
VIII.3.7	PWD SS304 Grab Bar (L-type)	2.00	sets		
VIII.3.8	PWD SS304 Flip-up Bar	2.00	sets		
VIII.3.9	PWD SS304 Urinal Grab Bar, 2 pcs per set	2.00	sets		
VIII.3.10	Stainless Steel 304/Brass, Faucet, 1/2" x 6", for sink	5.00	pc/s		
VIII.3.11	Floor Drain Stainless 6"x6"	7.00	pc/s		
VIII.3.12	Floor Drain Stainless 4"x4"	2.00	pc/s		
IX.	FIRE PROTECTION WORKS				
IX.1	Fire Protection				
	BLACK IRON PIPES, FITTINGS, VALVES AND ACCESSORIES				
	BI PIPES SCHEDULE 40 @ 6M, seamless (also including Drain Pipe Riser and Auto sprinkler riser)	1.00	lot		
	75 mm Ø		lengths		
	30 mm Ø		lengths		
	25 mm Ø		lengths		
	BI Elbow 90 Degrees				
	75 mm Ø		pcs		
	25 mm Ø		pcs		
	BI Tee Standard				
	75 mm Ø		pcs		
	25 mm Ø		pcs		

Item No.	Description	Qty	Unit	Adjusted Direct Unit Cost	Total Amount
	Bl Tee Reducer				
	75 mm Ø x 30 mm Ø		pcs		
	30 mm Ø x 25 mm Ø		pcs		
	Bell Reducer				
	50 X 100 mm Ø		pcs		
	30 X 25 mm Ø		pcs		
	Flanges				
	75 mm Ø		pcs		
	Union Patente				
	30 mm Ø		pcs		
	25 mm Ø		pcs		
	Drain Valve				
	75 mm Ø	1.00	pcs		
	Floor Control Valve				
	100 mm Ø	1.00	pcs		
	Auxiliary Drain Valve				
	75 mm Ø	1.00	pcs		
	Sight Glass				
	25 mm Ø	1.00	pcs		
	Supervisory Switch				
	100 mm Ø	1.00	pcs		
	Waterflow Switch				
	50 mm Ø	1.00	pcs		
	Pressure Gauge				
	Pressure Gauge	1.00	pcs		
	End Plug/End Cap				
	75 mm Ø	2.00	pcs		
	Sprinkler Heads & Accessories				
	Pendent Type: 135 Degrees to 165 Degrees	44.00	pcs		
	Others				
	Hangers and Supports	1.00	lot		
	Miscellaneous and Consumables	1.00	lot		
	Fire Hose Cabinets				
	Fire hose cabinets 100FT with 65mm dia hose valve and Fire extinguisher	2.00	pcs		
	Testing and Commissioning				
	Configuration, Testing and Commissioning, Documentation, Training and Orientation	1.00	lot		
X.	ELECTRICAL WORKS				
X.1	Roughing-Ins	1.00	lot		
X.1.1	20mm dia.uPVC Pipe		length/s		
X.1.2	20mm dia. uPVC male adapter with locknut		pcs		
X.1.3	25mm dia.uPVC Pipe		length/s		
X.1.4	25mm dia. uPVC male adapter with locknut		pcs		
X.1.5	20mm Corrugated Electrical Flexible Hose		lm		
X.1.6	20mm Electrical Flexible Hose Connector		pcs		
X.1.7	32mm dia.uPVC Pipe		length/s		
X.1.8	32mm dia. uPVC male adapter with locknut		pcs		
X.1.9	50mm dia.uPVC Pipe		length/s		
X.1.10	50mm dia. uPVC male adapter with locknut		pcs		
X.1.11	65mm dia.uPVC Pipe		length/s		
X.1.12	65mm dia. uPVC male adapter with locknut		pcs		
X.1.13	Junction Box with cover		pcs		
X.1.14	Utility Box		pcs		
X.1.15	Square Box		pcs		
X.1.16	Consumables	1.00	lot		
X.2	Wires and Cables	10,775.00	lm		
X.2.1	2.0 sq.mm THHN Wire	2,000.00	lm		
X.2.2	3.5 sq.mm THHN Wire	5,000.00	lm		
X.2.3	5.5 sq.mm THHN Wire	3,500.00	lm		
X.2.4	8.0 sq.mm THHN Wire	50.00	lm		
X.2.5	14.0 sq.mm THHN Wire	75.00	lm		
X.2.6	22.0 sq.mm THHN Wire	10.00	lm		
X.2.7	50.0 sq.mm THHN Wire	50.00	lm		
X.2.8	60.0 sq.mm THHN Wire	50.00	lm		
X.2.9	80.0 sq.mm THHN Wire	40.00	lm		
X.3	Lighting Fixtures	183.00	set/s		
X.3.1	4"Ø Downlight, with 11W LED Recessed Mounted	90.00	set/s		
X.3.2	2X18W Troffer LED Panel Type Lighting Fixture	57.00	set/s		
X.3.3	Emergency Light	20.00	set/s		
X.3.4	Exit Light	6.00	set/s		
X.3.5	30 watts LED Flood Light	10.00	set/s		
X.4	Wiring Devices	137.00	set/s		
X.4.1	Single pole switch with LED indicator, Flush type Modern Series	17.00	set/s		
X.4.2	Duplex switch with LED indicator Flush type Modern Series	15.00	set/s		

Printed Name and Signature of Proprietor/Manager/Authorized Representative

Item No.	Description	Qty	Unit	Adjusted Direct Unit Cost	Total Amount
X.4.3	Triplex switch with LED indicator Flush type Modern Series	10.00	set/s		
X.4.4	Single Universal Convenience Outlet, 3 Prong Modern Series, 16A, 230V	20.00	set/s		
X.4.5	Duplex Universal Convenience Outlet, 3 Prong Modern Series, 16A, 230V	58.00	set/s		
X.4.6	Duplex Universal Outlet, Floor Mounted Type, 16A, 230V	2.00	set/s		
X.4.7	GFCI Outlet	3.00	set/s		
X.4.8	ACU Outlet, Universal, 30A, 230V w/ Grounding-Type	12.00	set/s		
X.5	Panelboards and Circuit Breakers				
X.5.1	MDP	1.00	set/s		
	Assembled in NEMA 1 enclosure, wall mounted, Swing dead front, powder coated with terminal lugs in crimping type ready, with grounding busbar				
	Main : 300AT/300AF, 3P, 10KAIC, 230 V, BOLT-ON TYPE MCCB				
	Branches:				
	1 - 60AT/60AF, 2P, 10KAIC, 230 V, MCCB				
	2 - 125AT/125AF, 2P, 10KAIC, 230 V, MCCB				
X.5.2	GLP	1.00	set/s		
	Assembled in NEMA 1 enclosure, wall mounted, Swing dead front, powder coated with terminal lugs in crimping type ready, with grounding busbar				
	Main : 60AT/60AF, 3P, 10KAIC, 230 V, BOLT-ON TYPE MCCB				
	Branches:				
	12 - 20AT/60AF, 2P, 10KAIC, 230 V, MCB				
	2- SPACE				
X.5.3	GPP	1.00	set/s		
	Assembled in NEMA 1 enclosure, wall mounted, Swing dead front, powder coated with terminal lugs in crimping type ready, with grounding busbar				
	Main : 125AT/125AF, 3P, 10KAIC, 230 V, BOLT-ON TYPE MCCB				
	Branches:				
	18 - 30AT/60AF, 2P, 10KAIC, 230 V, MCB				
	2- SPACE				
X.5.4	GPACU	1.00	set/s		
	Assembled in NEMA 1 enclosure, wall mounted, Swing dead front, powder coated with terminal lugs in crimping type ready, with grounding busbar				
	Main : 125AT/125AF, 3P, 10KAIC, 230 V, BOLT-ON TYPE MCCB				
	Branches:				
	14 - 30AT/60AF, 2P, 10KAIC, 230 V, MCB				
	2- SPACE				
XI.	AUXILIARY WORKS				
XI.1	Fire Detection and Alarm System				
XI.1.1	Roughing-Ins / Wires:	1.00	lot		
XI.1.1.1	15mmØ EMT Pipe		pcs		
XI.1.1.2	15mmØ EMT Coupling		pcs		
XI.1.1.3	15mmØ EMT Connector		pcs		
XI.1.1.4	Pullbox		pcs		
XI.1.1.5	Metal Flexible Conduit 1/2"		lm		
XI.1.1.6	Straight Connector 1/2"		pcs		
XI.1.1.7	Junction Box w/ cover		pcs		
XI.1.1.8	Utility Box		pcs		
XI.1.1.9	Conduit Supports / Hangers		lot		
XI.1.1.10	1.25mm2 Twisted Pair		lm		
XI.1.1.11	Miscellaneous / Consumables	1.00	lot		
XI.1.2	Equipment:	43.00	sets		
XI.1.2.1	Smoke Detector	36.00	sets		
XI.1.2.2	24V Sounder & Strobe Light (Combined)	3.00	sets		
XI.1.2.3	Manual Push Station 24V	3.00	sets		
XI.1.2.4	Fire Alarm Control Panel 3 Zones, w/ back-up battery, 24V	1.00	sets		
XI.2	Paging System				
XI.2.1	Roughing-Ins / Wires:	1.00	lot		
XI.2.1.1	15mmØ uPVC Pipe		pcs		
XI.2.1.2	15mm dia. uPVC male adapter with locknut		pcs		
XI.2.1.3	Metal Flexible Conduit 1/2"		lm		
XI.2.1.4	Straight Connector 1/2"		pcs		
XI.2.1.5	Junction Box with cover		pcs		
XI.2.1.6	1.25mm2 Twisted Pair		lm		
XI.2.1.7	Consumables	1.00	lot		
XI.2.2	Equipments:	6.00	set		
XI.2.2.1	Ceiling Speaker	6.00	set		
XI.3	Telephone / LAN System				
XI.3.1	Roughing-Ins / Wires:	1.00	lot		

Printed Name and Signature of Proprietor/Manager/Authorized Representative

Item No.	Description	Qty	Unit	Adjusted Direct Unit Cost	Total Amount
XI.3.1.1	15mmØ uPVC Pipe		pcs		
XI.3.1.2	15mm dia. uPVC male adapter with locknut		pcs		
XI.3.1.3	Junction Box with cover		pcs		
XI.3.1.4	Utility Box with cover		pcs		
XI.3.1.5	UTP Cat 6 4pairs		lm		
XI.3.1.6	Consumables	1.00	lot		
XI.3.2	Devices:	6.00	set		
XI.3.2.1	Telephone and Data Outlet	6.00	set		
XI.4	CCTV System				
XI.4.1	Roughing-Ins / Wires:	1.00	lot		
XI.4.1.1	15mmØ uPVC Pipe		pcs		
XI.4.1.2	15mm dia. uPVC male adapter with locknut		pcs		
XI.4.1.3	Junction Box with cover		pcs		
XI.4.1.4	Utility Box with cover		pcs		
XI.4.1.5	UTP Cat 6 4pairs		lm		
XI.4.1.6	Consumables	1.00	lot		
XI.4.2	Devices:	4.00	set		
XI.4.2.1	IP Camera Dome Type	4.00	set		
XII.	MECHANICAL WORKS				
XII.1	Air Conditioning System	6.00	set/s		
XII.1.1	4.0 hp Ceiling Cassette Type Aircon	3.00	set/s		
XII.1.2	2.5hp Split Type Aircon	2.00	set/s		
XII.1.3	1.0 hp Split Type Aircon	1.00	set/s		
<b>TOTAL BID COST</b>					

Bid Amount in Figures:

Bid Amount in Words:

Name of the Construction Firm:

Printed Name of the Proprietor/Authorized Representative:

Signature of the Proprietor/Authorized Representative:

Date:

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

Printed Name and Signature of Proprietor/Manager/Authorized Representative

Item No.	Description	Qty	Unit	Adjusted Direct Unit Cost	Total Amount
XI.3.1.1	15mmØ uPVC Pipe		pcs		
XI.3.1.2	15mm dia. uPVC male adapter with locknut		pcs		
XI.3.1.3	Junction Box with cover		pcs		
XI.3.1.4	Utility Box with cover		pcs		
XI.3.1.5	UTP Cat 6 4pairs		lm		
XI.3.1.6	Consumables	1.00	lot		
XI.3.2	Devices:	6.00	set		
XI.3.2.1	Telephone and Data Outlet	6.00	set		
XI.4	CCTV System				
XI.4.1	Roughing-Ins / Wires:	1.00	lot		
XI.4.1.1	15mmØ uPVC Pipe		pcs		
XI.4.1.2	15mm dia. uPVC male adapter with locknut		pcs		
XI.4.1.3	Junction Box with cover		pcs		
XI.4.1.4	Utility Box with cover		pcs		
XI.4.1.5	UTP Cat 6 4pairs		lm		
XI.4.1.6	Consumables	1.00	lot		
XI.4.2	Devices:	4.00	set		
XI.4.2.1	IP Camera Dome Type	4.00	set		
XII.	MECHANICAL WORKS				
XII.1	Air Conditioning System	6.00	set/s		
XII.1.1	4.0 hp Ceiling Cassette Type Aircon	3.00	set/s		
XII.1.2	2.5hp Split Type Aircon	2.00	set/s		
XII.1.3	1.0 hp Split Type Aircon	1.00	set/s		
<b>TOTAL BID COST</b>					

Bid Amount in Figures:

Bid Amount in Words:

Name of the Construction Firm:

Printed Name of the Proprietor/Authorized Representative:

Signature of the Proprietor/Authorized Representative:

Date:

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

Printed Name and Signature of Proprietor/Manager/Authorized Representative

Item No.	Description	%	Qty	Unit	Direct Unit Cost	Total Direct Cost	Mark-Up in Percent		Total Mark-up	VAT (TDC+TMI) 5.00%	Total Indirect Cost	Total Amount	Adjusted Unit Cost
							OCM	Profit					
III. MASONRY WORKS													
III.1	Interior wall: 4" thk CHB w/ 10mm dia. vert. bar @ 0.40m o.c. w/ 10mm dia. hor. bar every 2nd layer		412.27	sq.m.									
III.1.1	Portland Cement			bags									
III.1.2	Fine Aggregates			cu.m.									
III.1.3	Concrete Hollow Blocks: 4", 450 Psi			pcs									
III.1.4	Deformed Bar: 10mmØ, Grade 60			lengths									
III.1.5	G.I. Tiewire #18			kgs.									
III.2	Exterior and Interior Plastering, 25mm thk including smooth finish (for the whole area)		824.55	sq.m.									
III.2.1	Masonry Cement			bags									
III.2.2	Fine Aggregates			cu.m.									
IV. CARPENTRY WORKS													
IV.1	Ceiling, 4.5 mm thk. Fiber Cement Board, 4' x 8' on Light Metal Framing Spaced @ 0.40m O.C. B.W.		618.81	sq.m.									
IV.1.1	4.5 mm thk. Fiber Cement Board, 4' x 8'			pcs									
IV.1.2	Fiber Board Screw, 20mm long			pcs									
IV.1.3	Double Furring, 19mm x 50mm x 5m, t=0.40mm			lengths									
IV.1.4	Plan Head Screw, 1/2", (Metal)			pcs									
IV.1.5	Carrying Channel, 12mm x 38mm x 3m, t=0.80mm			lengths									
IV.1.6	Wall Angle, 25mm x 25mm x 3.0m, t=0.40mm			lengths									
IV.1.7	Vertical Hanger (Carrying Channel)			lengths									
IV.1.8	Double furring clip			pcs									
IV.1.9	Concrete Nails, 1"			kls									
IV.2	Ceiling Coveight & Drop Ceiling Cladding, 4.50 mm thk. Fiber Cement Board, 4' x 8' on Light Metal Framing Spaced @ 0.40m O.C.		96.50	l.m.									
IV.2.1	4.50mm thk. Fiber Cement Board, 4' x 8'			pcs									
IV.2.2	Fiber Board Screw, 20mm long			pcs									
IV.2.3	Plan Head Screw, 1/2", (Metal)			pcs									
IV.2.4	Double Furring, 19mm x 50mm x 5m, t=0.40mm			lengths									
V. FINISHES													
*Note:													
V.1	Glazed Ceramic Floor Tiles 600mm x 600mm		458.00	sq.m.									
V.1.1	Non-skid, Ceramic Floor Tiles 600mm x 600mm			pcs.									
V.1.2	Tile Adhesive			bags									
V.1.3	Tile Grout, 2 kls.			packs									
V.2	Unglazed Ceramic Floor Tiles 600mm x 600mm		98.00	sq.m.									
V.2.1	Non-skid, Ceramic Floor Tiles 600mm x 600mm			pcs.									
V.2.2	Tile Adhesive			bags									
V.2.3	Tile Grout, 2 kls.			packs									
V.3	Non-skid Ceramic Wall Tiles 300mm x 300mm		13.50	sq.m.									
V.3.1	Non-skid Ceramic Wall Tiles 300mm x 300mm			pcs.									
V.3.2	Tile Adhesive			bags									
V.3.3	Tile Grout, 2 kls.			packs									
V.3.4	PVC Tile Trim, 2.4m			lengths									
V.4	Glossy/Polished, Ceramic Wall Tiles 300mm x 600mm (floor to ceiling)		77.56	sq.m.									

Item No.	Description	%	Qty	Unit	Direct Unit Cost	Total Direct Cost	Mark-Up in Percent		Total Mark-up	VAT (TDC+TMI)	Total Indirect Cost	Total Amount	Adjusted Unit Cost
							OCM	Profit					
V.4.1	Glossy/Polished, Ceramic Wall Tiles 300mm x 600mm			pcs.						5.00%			
V.4.2	Tile Adhesive			bags									
V.4.3	Tile Grout, 2 kls.			packs									
V.4.4	PVC Tile Trim, 2.4m			lengths									
V.5	Counter Sink Tiles, Glossy/Polished, Ceramic Tiles 600mm x 600mm		21.08	sq. m.									
VI.5.1	Concrete Sink Tiles, Glossy/Polished, Ceramic Tiles 600mm x 600mm			pcs.									
VI.5.2	Tile Adhesive			bags									
VI.5.3	Tile Grout, 2 kls.			packs									
VI.5.4	PVC Tile Trim, 2.4m			lengths									
V.6	Painting: Concrete Walls (Exterior)		314.32	sq. m.									
V.6.1	Semi-gloss Latex, (4L = 2 Coats)			gals									
V.6.2	Concrete neutralizer, 4L			gals									
V.6.3	Skimcoat			bags									
V.6.4	Patching Compound			kgs									
V.6.5	Primer Paint (2 Coats)			gal									
V.7	Painting: Concrete Walls including all opening's perimeter (Interior)		994.96	sq. m.									
V.7.1	Semi-gloss Latex, (4L = 2 Coats)			gals									
V.7.2	Concrete neutralizer, 4L			gals									
V.7.3	Skimcoat			bags									
V.7.4	Patching Compound			kgs									
V.7.5	Primer Paint (2 Coats)			gal									
V.8	Painting: Ceiling (Interior) including cove/light and drop ceilings		929.90	sq. m.									
V.8.1	White Flat Latex, 4L (2 coats)			gals									
V.8.2	Putty			gals									
V.8.3	Patching Compound			kgs									
V.8.4	Primer Paint (2 coats)			gal									
VII.	ARCHITECTURAL WORKS, SPECIALTIES & ACCESSORIES												
VII.1	Doors (incl. Jamb, Locks, Door Closer & Accessories)		28.00	Sets									
VII.1.1	DD1 (2.10m x 2.15m) 12mm thk. Tempered clear glass. Frameless door with 2" x 6" powder coated aluminum jamb with complete hardware accessories		2.00	sets									
VII.1.2	DD2 (1.50m x 2.15m) 1/4" thk. Clear Glass door on 50mm x 100mm powder-coated aluminum framed door with 2" x 6" powder coated aluminum jamb with complete hardware accessories		2.00	sets									
VII.1.3	DD3 (1.10m x 2.15m) 1/4" thk. Clear Glass door on 50mm x 100mm powder-coated aluminum framed door with 2" x 6" powder coated aluminum jamb with complete hardware accessories		2.00	sets									
VII.1.4	DD4 (1.70m x 2.10m) Hollow core metal flush type swinging door w/ 500mmx800mm view window on 6mm thk. wired glass with 2" x 6" steel jamb on double action hinges and complete hardware accessories in automotive finish		3.00	sets									
VII.1.5	DD5 (1.50m x 2.10m) Hollow core metal flush type swinging door w/ 500mmx800mm view window on 6mm thk. wired glass with 2" x 6" steel jamb on double action hinges and complete hardware accessories in automotive finish		1.00	sets									

Printed Name and Signature of Proprietor/Manager/Authorized Representative

Item No.	Description	%	Qty	Unit	Direct Unit Cost	Total Direct Cost	Mark-Up in Percent		Total Mark-up	VAT (TDC+TMIU) 5.00%	Total Indirect Cost	Total Amount	Adjusted Unit Cost
							OCM	Profit					
VII.1.6	D06 (1.50m x 2.10m) Hollow core metal flush type swinging door w/ 500mmx800mm view window on 6mm thick wired glass with 2" x 6" steel jamb on double action hinges and complete hardware accessories in automotive finish		3.00	sets									
VII.1.7	D07 (1.10m x 2.10m) Solid panel door w/ 2" x 6" wood jamb already installed, provide w/ ball bearing, full mortise on heavy duty hinges and complete hardware accessories in automotive finish		2.00	sets									
VII.1.8	D08 (0.80m x 2.10m) Solid panel door w/ 2" x 6" wood jamb already installed, provide w/ ball bearing, full mortise on heavy duty hinges and complete hardware accessories in automotive finish		8.00	sets									
VII.1.9	D09 (0.90m x 2.10m) Solid panel door w/ 2" x 6" wood jamb already installed, provide w/ ball bearing, full mortise on heavy duty hinges and complete hardware accessories in automotive finish		4.00	sets									
VII.1.10	D10 (0.80m x 2.10m) Double swing 1/2" Aluminum lower door panel painted finish w/ 2" x 6" steel jamb w/ double action heavy duty hinges w/ complete hardware accessories in automotive finish		1.00	sets									
VII.2	Windows (Incl. Jamb, Locks & Accessories)		6.00	Sets									
VII.2.1	W01 - (1.80m x 1.20m) 1/4" thick clear glass sliding window powder-coated aluminum frame w/ complete hardware accessories		3.00	sets									
VII.2.2	W02 - (1.25m x 0.60m) 1/4" thick clear glass sliding window powder-coated aluminum frame w/ complete hardware accessories		1.00	sets									
VII.2.3	W03 - (1.60m x 1.00m) 1/4" thick clear glass fixed window on powder-coated aluminum frame w/ complete hardware accessories		1.00	sets									
VII.2.4	W04 - (0.83m x 1.00m) 1/4" thick clear glass fixed window on powder-coated aluminum frame w/ complete hardware accessories		1.00	sets									
VII.3	Building/Room Signages/Wayfinding Systems		32.00	Sets									
VII.3.1	Room Identification Sign - CHIEF NURSE OFFICE, 6mm thick Frosted Acrylic		4.00	sets									
VII.3.2	Room Identification Sign - PULMONARY UNIT, 6mm thick Frosted Acrylic		1.00	sets									
VII.3.3	Room Identification Sign - PHYSICAL THERAPIST ROOM, 6mm thick Frosted Acrylic		1.00	sets									
VII.3.4	Room Identification Sign - JANITORS CLOSET, 6mm thick Frosted Acrylic		2.00	sets									
VII.3.5	Room Identification Sign - ELECTRICAL ROOM, 6mm thick Frosted Acrylic		2.00	sets									
VII.3.6	Room Identification Sign - BUSINESS OFFICE, 6mm thick Frosted Acrylic		2.00	sets									
VII.3.7	Room Identification Sign - STAKEHOLDERS OFFICE, 6mm thick Frosted Acrylic		3.00	sets									
VII.3.8	Room Identification Sign - TREATMENT AREA, 6mm thick Frosted Acrylic		1.00	sets									
VII.3.9	Room Identification Sign - DOCTORS OFFICE, 6mm thick Frosted Acrylic		1.00	sets									
VII.3.10	Room Identification Sign - PANTRY, 6mm thick Frosted Acrylic		1.00	sets									
VII.3.11	Room Identification Sign - WATER TREATMENT ROOM, 6mm thick Frosted Acrylic		3.00	sets									

Printed Name and Signature of Proprietor/Manager/Authorized Representative

Item No.	Description	%	Qty	Unit	Direct Unit Cost	Total Direct Cost	Mark-Up in Percent		Total Mark-up	VAT (TDC+TMI) 5.00%	Total Indirect Cost	Total Amount	Adjusted Unit Cost
							OCM	Profit					
VII.3.12	Room Identification Sign - REPROCESSING ROOM, 6mm thick Frosted Acrylic		1.00	sets									
VII.3.13	Room Identification Sign - WASTE HOLDING AREA, 6mm thick Frosted Acrylic		2.00	sets									
VII.3.14	Room Identification Sign - NURSE STATION, 6mm thick Frosted Acrylic		3.00	sets									
VII.3.19	Restroom Identification - PWD Toilet, 6mm thick Frosted Acrylic		1.00	sets									
VII.3.20	Restroom Identification - All Gender Toilet, 6mm thick Frosted Acrylic		2.00	sets									
VII.3.21	Restroom Identification - Staff Toilet, 6mm thick Frosted Acrylic		1.00	sets									
VII.3.22	Emergency Exit Plan, 6mm thick Frosted Acrylic		1.00	sets									
VIII	PLUMBING WORKS												
VIII.1	Wasteline Pipings, S1000, Fittings & Accessories		1.00	lot									
VIII.1.1	PVC Pipe 4"Ø S1000 Sanitary Pipe			lengths									
VIII.1.2	PVC Pipe 2"Ø S1000 Sanitary Pipe			lengths									
VIII.1.3	PVC Wye Reducer 8"x4"			pcs									
VIII.1.4	PVC Wye Reducer 4"x2"			pcs									
VIII.1.5	PVC Wye 4"x4"			pcs									
VIII.1.6	PVC Wye 2"x2"			pcs									
VIII.1.7	PVC Elbow 4"x60			pcs									
VIII.1.8	PVC Elbow 4"x45			pcs									
VIII.1.9	PVC Elbow 2"x45			pcs									
VIII.1.10	PVC Elbow 2"x90			pcs									
VIII.1.11	PVC Tee 4"x4"			pcs									
VIII.1.12	PVC Tee 4"x2"			pcs									
VIII.1.13	PVC Tee 2"x2"			pcs									
VIII.1.14	PVC P-Trap 4"			pcs									
VIII.1.15	PVC P-Trap 2"			pcs									
VIII.1.16	PVC Bottle-Trap 2"			pcs									
VIII.1.17	PVC Coupling 4"Ø			pcs									
VIII.1.18	PVC Coupling 2"Ø			pcs									
VIII.1.19	PVC Clean Out 4"Ø			pcs									
VIII.1.20	PVC Clean Out 2"Ø			pcs									
VIII.1.21	Stainless Steel Vent Cap 4"Ø			pcs									
VIII.1.22	Stainless Steel Vent Cap 2"Ø			pcs									
VIII.1.23	Solvent Cement, 200cc			liters									
VIII.1.24	Sealant (Vulcaseal)			liters									
VIII.2	Waterline Pipings, Fittings & Accessories		1.00	lot									
VIII.2.1	PPR Pipe 2"Ø			lengths									
VIII.2.2	PPR Pipe 1 1/2"Ø			lengths									
VIII.2.3	PPR Pipe 1/2"			lengths									
VIII.2.4	PPR Elbow 2" Plain			pcs									
VIII.2.5	PPR Elbow 1 1/2" Plain			pcs									
VIII.2.6	PPR Elbow 1/2" plain			pcs									
VIII.2.7	PPR Tee 2"			pcs									
VIII.2.8	PPR Tee 1 1/2"			pcs									
VIII.2.9	PPR Tee 1/2" plain			pcs									
VIII.2.10	PPR Coupling 1/2"			pcs									
VIII.2.11	PPR Female Adaptor 1/2"			pcs									
VIII.2.12	PPR Reducer 2" x 1/2"			pcs									
VIII.2.13	PPR Reducer 1 1/2" x 1/2"			pcs									
VIII.2.14	PPR Gate Valve 1/2"			pcs									
VIII.2.15	Angle Valve 1/2"x1/2"			pcs									
VIII.2.16	Flexible Hose 1/2"x1/2"x16"			pcs									
VIII.2.17	Teflon Tape 1"			pcs									
VIII.3	Plumbing Fixtures		1.00	lot									
	* Submit samples for approval prior to installation												
	** Faucets, valves & other accessories shall be Japan, U.S., & E.U. made												

Printed Name and Signature of Proprietor/Manager/Authorized Representative

Item No.	Description	%	Qty	Unit	Direct Unit Cost	Total Direct Cost	Mark-Up in Percent		Total Mark-up	VAT (TDC+TMU) 5.00%	Total Indirect Cost	Total Amount	Adjusted Unit Cost
							OCM	Profit					
VIII.3.1	Two-Piece Water Closet/s (push button, 4/6 liters water saver) with wall-mounted Semi-recessed Ceramic Tissue Holder, wall-mounted Semi-recessed Ceramic Soap Holder, complete accessories		7.00	set/s									
VIII.3.2	Lavatory with Pedestal w/ faucet and w/ Complete Fittings & Accessories		8.00	set/s									
VIII.3.3	600x400x200x0.8 mm Stainless Steel Single Bowl Kitchen Sink w/ Complete Fittings & Accessories		5.00	set/s									
VIII.3.4	Urinal w/ Complete Fittings & Accessories		2.00	set/s									
VIII.3.5	SS 304 Towel Bar		7.00	pcs									
VIII.3.6	Stainless Faucet		8.00	pcs									
VIII.3.7	PWD SS304 Grab Bar (L-type)		2.00	sets									
VIII.3.8	PWD SS304 Flip-up Bar		2.00	sets									
VIII.3.9	PWD SS304 Urinal Grab Bar, 2 pcs per set		2.00	sets									
VIII.3.10	Stainless Steel 304/Bass, Faucet, 1/2" x 6", for sink		5.00	pcs									
VIII.3.11	Floor Drain Stainless 6"x6"		7.00	pcs									
VIII.3.12	Floor Drain Stainless 4"x4"		2.00	pcs									
IX.	FIRE PROTECTION WORKS												
IX.1	Fire Protection												
	BLACK IRON PIPES, FITTINGS, VALVES AND ACCESSORIES												
	BI PIPES SCHEDULE 40 @ 6M, seamless (also including Drain Pipe Riser and Auto sprinkler riser)		1.00	lot									
	75 mm Ø			lengths									
	30 mm Ø			lengths									
	25 mm Ø			lengths									
	BI Elbow 90 Degrees												
	75 mm Ø			pcs									
	25 mm Ø			pcs									
	BI Tee Standard												
	75 mm Ø			pcs									
	25 mm Ø			pcs									
	BI Tee Reducer												
	75 mm Ø x 30 mm Ø			pcs									
	30 mm Ø x 25 mm Ø			pcs									
	Bell Reducer												
	50 X 100 mm Ø			pcs									
	30 X 25 mm Ø			pcs									
	Flanges												
	75 mm Ø			pcs									
	Union Patente												
	30 mm Ø			pcs									
	25 mm Ø			pcs									
	Drain Valve												
	75 mm Ø		1.00	pcs									
	Floor Control Valve												
	100 mm Ø		1.00	pcs									
	Auxiliary Drain Valve												
	75 mm Ø		1.00	pcs									
	Sight Glass												
	25 mm Ø		1.00	pcs									
	Supervisory Switch												
	100 mm Ø		1.00	pcs									
	Waterflow Switch												
	50 mm Ø		1.00	pcs									
	Pressure Gauge												
	Pressure Gauge		1.00	pcs									
	End Plug/End Cap												
	75 mm Ø		2.00	pcs									
	Sprinkler Heads & Accessories												
	Pendent Type: 135 Degrees to 165 Degrees		44.00	pcs									
	Others												
	Hangers and Supports		1.00	lot									

Printed Name and Signature of Proprietor/Manager/Authorized Representative

Item No.	Description	%	Qty	Unit	Direct Unit Cost	Total Direct Cost	Mark-Up in Percent		Total Mark-up	VAT (TDC+THU) 5.00%	Total Indirect Cost	Total Amount	Adjusted Unit Cost
							OCM	Profit					
	Miscellaneous and Consumables		1.00	lot									
	Fire Hose Cabinets												
	Fire hose cabinets 100FT with 65mm dia hose valve and Fire extinguisher		2.00	pcsa									
	Testing and Commissioning												
	Configuration, Testing and Commissioning, Documentation, Training and Orientation		1.00	lot									
X	ELECTRICAL WORKS												
X.1	Roughing-In		1.00	lot									
X.1.1	20mm dia uPVC Pipe			length's									
X.1.2	20mm dia. uPVC male adapter with locknut			pcs									
X.1.3	25mm dia.uPVC Pipe			length's									
X.1.4	25mm dia. uPVC male adapter with locknut			pcs									
X.1.5	20mm Corrugated Electrical Flexible Hose			lm									
X.1.6	20mm Electrical Flexible Hose Connector			pcs									
X.1.7	32mm dia.uPVC Pipe			length's									
X.1.8	32mm dia. uPVC male adapter with locknut			pcs									
X.1.9	50mm dia.uPVC Pipe			length's									
X.1.10	50mm dia. uPVC male adapter with locknut			pcs									
X.1.11	65mm dia.uPVC Pipe			length's									
X.1.12	65mm dia. uPVC male adapter with locknut			pcs									
X.1.13	Junction Box with cover			pcs									
X.1.14	Utility Box			pcs									
X.1.15	Square Box			pcs									
X.1.16	Consumables		1.00	lot									
X.2	Wires and Cables		10,775.00	lm									
X.2.1	2.0 sq.mm THHN Wire		2,000.00	lm									
X.2.2	3.5 sq.mm THHN Wire		5,000.00	lm									
X.2.3	5.5 sq.mm THHN Wire		3,500.00	lm									
X.2.4	8.0 sq.mm THHN Wire		50.00	lm									
X.2.5	14.0 sq.mm THHN Wire		75.00	lm									
X.2.6	22.0 sq.mm THHN Wire		10.00	lm									
X.2.7	80.0 sq.mm THHN Wire		50.00	lm									
X.2.8	60.0 sq.mm THHN Wire		60.00	lm									
X.2.9	80.0 sq.mm THHN Wire		40.00	lm									
X.3	Lighting Fixtures		183.00	set's									
X.3.1	4"Ø Downlight, with 11W LED Recessed Mounted		90.00	set's									
X.3.2	2X18W Troffer LED Panel Type Lighting Fixture		57.00	set's									
X.3.3	Emergency Light		20.00	set's									
X.3.4	Exit Light		6.00	set's									
X.3.5	30 watts LED Flood Light		10.00	set's									
X.4	Wiring Devices		137.00	set's									
X.4.1	Single pole switch with LED indicator, Flush type Modern Series		17.00	set's									
X.4.2	Duplex switch with LED indicator Flush type Modern Series		15.00	set's									
X.4.3	Triplex switch with LED indicator Flush type Modern Series		10.00	set's									
X.4.4	Single Universal Convenience Outlet, 3 Prong Modern Series, 16A, 230V		20.00	set's									
X.4.5	Duplex Universal Convenience Outlet, 3 Prong Modern Series, 16A, 230V		58.00	set's									
X.4.6	Duplex Universal Outlet,Floor Mounted Type, 16A, 230V		2.00	set's									
X.4.7	GFCI Outlet		3.00	set's									
X.4.8	ACU Outlet, Universal, 30A, 230V w/ Grounding-Type		12.00	set's									
X.5	Panelboards and Circuit Breakers												
X.5.1	MDP		1.00	set's									

Printed Name and Signature of Proprietor/Manager/Authorized Representative

Item No.	Description	%	Qty	Unit	Direct Unit Cost	Total Direct Cost	Mark-Up in Percent		Total Mark-up	VAT (TDC+TMI) 5.00%	Total Indirect Cost	Total Amount	Adjusted Unit Cost
							OCM	Profit					
	Assembled in NEMA 1 enclosure, wall mounted, Swing dead front, powder coated with terminal lugs in crimping type ready, with grounding busbar												
	Main : 300AT/300AF, 3P, 10KAIC, 230 V, BOLT-ON TYPE MCCB												
	Branches:												
	1 - 60AT/60AF, 2P, 10KAIC, 230 V, MCCB												
	2 - 125AT/125AF, 2P, 10KAIC, 230 V, MCCB												
X.5.2	GLP		1.00	sets									
	Assembled in NEMA 1 enclosure, wall mounted, Swing dead front, powder coated with terminal lugs in crimping type ready, with grounding busbar												
	Main : 60AT/60AF, 3P, 10KAIC, 230 V, BOLT-ON TYPE MCCB												
	Branches:												
	12 - 20AT/20AF, 2P, 10KAIC, 230 V, MCB												
	2- SPACE												
X.5.3	GPP		1.00	sets									
	Assembled in NEMA 1 enclosure, wall mounted, Swing dead front, powder coated with terminal lugs in crimping type ready, with grounding busbar												
	Main : 125AT/125AF, 3P, 10KAIC, 230 V, BOLT-ON TYPE MCCB												
	Branches:												
	18 - 30AT/30AF, 2P, 10KAIC, 230 V, MCB												
	2- SPACE												
X.5.4	GPACU		1.00	sets									
	Assembled in NEMA 1 enclosure, wall mounted, Swing dead front, powder coated with terminal lugs in crimping type ready, with grounding busbar												
	Main : 125AT/125AF, 3P, 10KAIC, 230 V, BOLT-ON TYPE MCCB												
	Branches:												
	14 - 30AT/30AF, 2P, 10KAIC, 230 V, MCB												
	2- SPACE												
XI	AUXILIARY WORKS												
XI.1	Fire Detection and Alarm System												
XI.1.1	Roughing-ins / Wires:		1.00	lot									
XI.1.1.1	15mmØ EMT Pipe			pcs									
XI.1.1.2	15mmØ EMT Coupling			pcs									
XI.1.1.3	15mmØ EMT Connector			pcs									
XI.1.1.4	Pullbox			pcs									
XI.1.1.5	Metal Flexible Conduit 1/2"			lm									
XI.1.1.6	Straight Connector 1/2"			pcs									
XI.1.1.7	Junction Box w/ cover			pcs									
XI.1.1.8	Utility Box			pcs									
XI.1.1.9	Conduit Supports / Hangers			lot									
XI.1.1.10	1.25mmØ Twisted Pair			lm									
XI.1.1.11	Miscellaneous / Consumables		1.00	lot									
XI.1.2	Equipment:		43.00	sets									
XI.1.2.1	Smoke Detector		36.00	sets									
XI.1.2.2	24V Sounder & Strobe Light (Combined)		3.00	sets									
XI.1.2.3	Manual Push Station 24V		3.00	sets									
XI.1.2.4	Fire Alarm Control Panel 3 Zones, w/ back-up battery, 24V		1.00	sets									
XI.2	Paging System												
XI.2.1	Roughing-ins / Wires:		1.00	lot									
XI.2.1.1	15mmØ uPVC Pipe			pcs									

Printed Name and Signature of Proprietor/Manager/Authorized Representative

Item No.	Description	%	Qty	Unit	Direct Unit Cost	Total Direct Cost	Mark-Up in Percent		Total Mark-up	VAT (TDC+TMI)	Total Indirect Cost	Total Amount	Adjusted Unit Cost
							OCM	Profit					
XI.2.1.2	15mm dia. uPVC male adapter with locknut			pcs						5.00%			
XI.2.1.3	Metal Flexible Conduit 1/2"			lm									
XI.2.1.4	Straight Connector 1/2"			pcs									
XI.2.1.5	Junction Box with cover			pcs									
XI.2.1.6	1.25mm <sup>2</sup> Twisted Pair			lm									
XI.2.1.7	Consumables		1.00	lot									
XI.2.2	Equipments:		6.00	set									
XI.2.2.1	Ceiling Speaker		6.00	set									
XI.3	Telephone / LAN System												
XI.3.1	Roughing-ins / Wires:		1.00	lot									
XI.3.1.1	15mm <sup>2</sup> uPVC Pipe			pcs									
XI.3.1.2	15mm dia. uPVC male adapter with locknut			pcs									
XI.3.1.3	Junction Box with cover			pcs									
XI.3.1.4	Utility Box with cover			pcs									
XI.3.1.5	UTP Cat 6 4pairs			lm									
XI.3.1.6	Consumables		1.00	lot									
XI.3.2	Devices:		6.00	set									
XI.3.2.1	Telephone and Data Outlet		6.00	set									
XI.4	CCTV System												
XI.4.1	Roughing-ins / Wires:		1.00	lot									
XI.4.1.1	15mm <sup>2</sup> uPVC Pipe			pcs									
XI.4.1.2	15mm dia. uPVC male adapter with locknut			pcs									
XI.4.1.3	Junction Box with cover			pcs									
XI.4.1.4	Utility Box with cover			pcs									
XI.4.1.5	UTP Cat 6 4pairs			lm									
XI.4.1.6	Consumables		1.00	lot									
XI.4.2	Devices:		4.00	set									
XI.4.2.1	IP Camera Dome Type		4.00	set									
XII	MECHANICAL WORKS												
XII.1	Air Conditioning System		6.00	set/s									
XII.1.1	4.0 hp Ceiling CassetteType Aircon		3.00	set/s									
XII.1.2	2.5hp Split Type Aircon		2.00	set/s									
XII.1.3	1.0 hp Split Type Aircon		1.00	set/s									
	<b>TOTAL</b>	<b>100.00%</b>											

Bid Amount in Figures:

Bid Amount in Words:

Name of the Construction Firm:

Printed Name of the Proprietor/Authorized Representative:

Signature of the Proprietor/Authorized Representative:

Date:

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_













		W/O												
				Gross Area =										
				Net Area =										
<b>V.8 Painting, Ceiling (Interior) Including Cove-light and drop ceilings</b>		<b>929.90</b>		<b>sq.m.</b>						<b>Total - Painting: Concrete Walls (Interior)</b>		<b>P</b>		
V.8.1	Walls Paint Labor, 4L (2 coats)													
V.8.2	Putty													
V.8.3	Painting Compound													
V.8.4	Primer Paint (2 coats)													
										<b>Total - Painting: Ceiling (Interior)</b>		<b>P</b>		
										<b>Total - Finishes Works</b>		<b>P</b>		
<b>VII. ARCHITECTURAL WORKS, SPECIALTIES &amp; ACCESSORIES</b>														
<b>VII.1 Doors (incl. Jamb, Locks, Door Closer &amp; Accessories)</b>		<b>26.00</b>		<b>Sets</b>										
VII.1.1	D01 (2.10m x 2.10m) 12mm thk. Tempered clear glass frameless door with 2" x 6" powder coated aluminum jamb with complete hardware accessories													
VII.1.2	D02 (1.50m x 2.10m) 14th thk. Clear Glass door on 50mm x 100mm powder-coated aluminum framed door with 2" x 6" powder coated aluminum jamb with complete hardware accessories													
VII.1.3	D03 (1.50m x 2.10m) 14th thk. Clear Glass door on 50mm x 100mm powder-coated aluminum framed door with 2" x 6" powder coated aluminum jamb with complete hardware accessories													
VII.1.4	D04 (1.70m x 2.10m) Hollow core metal flush type swinging door w/ 500mmx800mm view window on 6mm thk wired glass with 2" x 6" steel jamb on double action hinges and complete hardware accessories in automotive finish													
VII.1.5	D05 (1.50m x 2.10m) Hollow core metal flush type swinging door w/ 500mmx800mm view window on 6mm thk wired glass with 2" x 6" steel jamb on double action hinges and complete hardware accessories in automotive finish													
VII.1.6	D06 (1.50m x 2.10m) Hollow core metal flush type swinging door w/ 500mmx800mm view window on 6mm thk wired glass with 2" x 6" steel jamb on double action hinges and complete hardware accessories in automotive finish													
VII.1.7	D07 (1.50m x 2.10m) Solid panel door w/ 2" x 6" wood jamb already installed, provide w/ full bearing, full mortise on heavy duty hinges and complete hardware accessories in automotive finish													
VII.1.8	D08 (0.90m x 2.10m) Solid panel door w/ 2" x 6" wood jamb already installed, provide w/ full bearing, full mortise on heavy duty hinges and complete hardware accessories in automotive finish													
VII.1.9	D09 (0.90m x 2.10m) Solid panel door w/ 2" x 6" wood jamb already installed, provide w/ full bearing, full mortise on heavy duty hinges and complete hardware accessories in automotive finish													
VII.1.10	D10 (0.90m x 2.10m) Double swing 1/2" Aluminum louver door panel painted finish w/ 2" x 6" steel jamb w/ double action heavy duty hinges w/ complete hardware accessories in automotive finish													
												<b>Total - Doors</b>		
<b>VII.2 Windows (incl. Jamb, Locks &amp; Accessories)</b>		<b>6.00</b>		<b>Sets</b>										
VII.2.1	W01 - (1.80m x 1.20m) 14th thk clear glass sliding window powder-coated aluminum frame w/ complete hardware accessories													
VII.2.2	W02 - (1.20m x 0.90m) 14th thk clear glass sliding window powder-coated aluminum frame w/ complete hardware accessories													
VII.2.3	W03 - (1.80m x 1.00m) 14th thk clear glass fixed window on powder-coated aluminum frame w/ complete hardware accessories													
VII.2.4	W04 - (0.90m x 1.00m) 14th thk clear glass fixed window on powder-coated aluminum frame w/ complete hardware accessories													
												<b>Total - Windows</b>		
<b>VII.3 Building/Room Signages/Wayfinding Systems</b>		<b>32.00</b>		<b>Sets</b>										
VII.3.1	Room Identification Sign - CHIEF NURSE OFFICE, 6mm thick Frosted Acrylic													
VII.3.2	Room Identification Sign - PULMONARY UNIT, 6mm thick Frosted Acrylic													
VII.3.3	Room Identification Sign - PHYSICAL THERAPIST ROOM, 6mm thick Frosted Acrylic													
VII.3.4	Room Identification Sign - JANITORS CLOSET, 6mm thick Frosted Acrylic													
VII.3.5	Room Identification Sign - ELECTRICAL ROOM, 6mm thick Frosted Acrylic													
VII.3.6	Room Identification Sign - BUSINESS OFFICE, 6mm thick Frosted Acrylic													
VII.3.7	Room Identification Sign - STORAGE/DESK OFFICE, 6mm thick Frosted Acrylic													
VII.3.8	Room Identification Sign - TREATMENT AREA, 6mm thick Frosted Acrylic													
VII.3.9	Room Identification Sign - DOC TONS OFFICE, 6mm thick Frosted Acrylic													
VII.3.10	Room Identification Sign - PHARM, 6mm thick Frosted Acrylic													
VII.3.11	Room Identification Sign - WATER TREATMENT ROOM, 6mm thick Frosted Acrylic													
VII.3.12	Room Identification Sign - RECEPTIONS ROOM, 6mm thick Frosted Acrylic													
VII.3.13	Room Identification Sign - WASTE HOLDING AREA, 6mm thick Frosted Acrylic													
VII.3.14	Room Identification Sign - NURSE STATION, 6mm thick Frosted Acrylic													
VII.3.15	Restroom Identification - PWG Toilet, 6mm thick Frosted Acrylic													
VII.3.20	Restroom Identification - All Gender Toilet, 6mm thick Frosted Acrylic													
VII.3.21	Restroom Identification - Staff Toilet, 6mm thick Frosted Acrylic													
VII.3.22	Emergency Exit Plan, 6mm thick Frosted Acrylic													
												<b>Total - Building/Room Signages/Wayfinding Systems</b>		
												<b>Total - Architectural Works, Specialties and Accessories</b>		
<b>VIII. PLUMBING WORKS</b>		<b>1.00</b>		<b>lot</b>										
<b>VIII.1 Wasteline Fittings, 51000, Fittings &amp; Accessories</b>		<b>1.00</b>		<b>lot</b>										
VIII.1.1	PVC Pipe 4" S 1000 Sanitary Pipe													
VIII.1.2	PVC Pipe 2" S 1000 Sanitary Pipe													
VIII.1.3	PVC Wye Reducer 4"x2"													
VIII.1.4	PVC Wye Reducer 4"x2"													
VIII.1.5	PVC Wye 4"x4"													
VIII.1.6	PVC Wye 2"x2"													
VIII.1.7	PVC Elbow 4"x4"													
VIII.1.8	PVC Elbow 4"x4"													
VIII.1.9	PVC Elbow 2"x4"													
VIII.1.10	PVC Elbow 2"x4"													
VIII.1.11	PVC Tee 4"x4"													
VIII.1.12	PVC Tee 4"x4"													
VIII.1.13	PVC Tee 2"x2"													
VIII.1.14	PVC Tee 4"x4"													
VIII.1.15	PVC Tee 4"x4"													
VIII.1.16	PVC Tee 4"x4"													
VIII.1.17	PVC Tee 4"x4"													

Printed Name and Signature of Proprietor/Manager/Authorized Representative





