

QCDD TEST

Date: 08.11.2017

1. Draw a Single Line Diagram for the Warehouse and Accommodation System on for a complete Fire Alarm System incorporating all the required initiating devices, fire alarm control panel, interface units, wiring details notification appliance system etc
2. Standard for the control units and accessories for fire alarm system.
Ans. ANSI/UL864
3. Engine-driven Generator shall be inspected, tested and maintained.
Ans. Monthly
4. The color code for the Ordinary type rate of rise Heat Detector.
Ans. Uncolor
5. Indicates a recommendation or that which is advised but not required.
Ans. Should
6. Abnormal condition that possesses a threat to life, property or mission and time is available for investigation.
Ans. Pre-alarm condition
7. Fire-gas Detectors and other Fire Detectors shall be tested as prescribed by the manufacturer and as necessary for the application.
Ans. Annually
8. If impairment is not corrected at the conclusion of the system inspection, testing or maintenance, the system owner shall be informed with in.
Ans. 24 Hrs.
9. All Fire Alarm Equipment shall be inspected, tested or maintained.
Ans. Annually
10. Emergency Communications Equipment shall be inspected, tested and maintained.
Ans. Annually
11. Projected Beam type Detectors shall be inspected, tested etc
Ans. Annually
12. Installation, inspection, testing and maintenance of Fire Alarm System shall be carried out as per.
Ans. Manufacturer's Published Documents/Instructions.