



Republic of the Philippines
Department of Education
NATIONAL CAPITAL REGION
SCHOOLS DIVISION OF PARAÑAQUE CITY
BACLARAN ELEMENTARY SCHOOL UNIT-I

**INVITATION TO SUBMIT SEALED QUOTATION FOR
FABRICATION/INSTALLATION OF WAITING AREA**

DATE : JANUARY 27, 2022
RFQ: No.: 2022-001

The **Department of Education (DepEd) Schools Division of Parañaque City Baclaran Elementary School I** invites all interested parties to apply and submit separate sealed bids/quotation for the Fabrication/Installation of Waiting Area of **Baclaran Elementary School I** located at Pinaglabanan St. Brgy. Baclaran, Parañaque City. The Approved Budget of Contract (ABC) is **One Hundred Thirty-Eight Thousand Seven Hundred Fifty-Three & Two Centavos (Php 138,753.02)**.

Bid/Quotation submission and Opening of Bids/Quotation will be on **or before February 2, 2022, 9:00 a.m. Principal's Office, Baclaran Elem. School I Pinaglabanan St. Brgy. Baclaran Parañaque City** with sealed bids/quotation proposal to be open in the presence of School Bids and Awards Committee. You can also email us at bes1.pque@deped.gov.ph. For more information, please call us at Telephone No. 88539350. **Late bids shall not be accepted.**

Other information may be obtained at Baclaran Elementary School I *BAC Secretariat*, prior to the date of scheduled bidding/opening of bids/sealed quotations.

Baclaran Elementary School I reserve the right to reject any or all bids without offering any reason, waive any required formality and award the contract to the bidder whose proposal is deemed most advantageous to the agency. Furthermore, Baclaran Elementary School I assume no obligation to compensate or indemnify the bidder for any expenses or losses that may be incurred in the preparation of bids nor guarantee that award will be made.

JADELWISA E. OCAMPO
SBAC- Chairman



Address: Pinaglabanan St., Baclaran, Parañaque City
Telephone No.: 8-853-93-50
Email: bes1.pque @deped.gov.ph



Republic of the Philippines
Department of Education
 NATIONAL CAPITAL REGION
 SCHOOLS DIVISION OF PARAÑAQUE CITY
 BACLARAN ELEMENTARY SCHOOL UNIT-I

Particulars

Program of Works

PROJECT : FABRICATION / INNSTALLATION OF WAITING AREA

LOCATION : BACLARAN ELEMENTARY SCHOOL UNIT 1

OWNER : DEPARTMENT OF EDUCATION

SUBJECT : APPROVED AGENCY ESTIMATE

I.D NO .	DESCRIPTION	UNIT	QTY	UNIT COST		TOTAL COST		GRAND TOTAL	
				MATERIA L	LABO R	MATERIA L	LABO R		
	GENERAL REQUIREMENTS								
	Mobilization / temporary Structures, Utilities and Services Demobilization	lot	1						
	Safety and Health	lot	1						
	Subtotal								
B	Earthworks								
	Clearing and Grubbing	sq.m	20						
	Structural Excavation	cu. m	5.47						
	Backfilling and Compaction	cu. m	23.6						
	Gravel Bedding G-1	cu. m	0.29						
	Select Fill	cu. m	1						
	Sub-Total								
C	Concreting Works								
	Column Footing	cu. m	0.43						
	Portland Cement	bag	0.5						
	Crushed Gravel 1	cu. m	0.25						
	Washed Sand	cu. m	1.44						
	Wall Footing	cu. m	13						
	Portland Cement	bag	1.5						
	Crushed Gravel 1	cu. m	0.75						
	Washed Sand	cu. m	0.32						
	Column	cu. m	0.3						
	Portland Cement	bag	0.5						
	Crushed Gravel 3/4"	cu. m	0.25						
	Washed Sand	cu. m	3.6						
	Slab on Grade	cu. m	33						
	Portland Cement	bag	3.75						
	Crushed Gravel 3/4"	cu. m	2						



Address: Pinaglabanan St., Bacclaran, Parañaque City
Telephone No.: 8-853-93-50
Email: bes1.pque @deped.gov.ph



Republic of the Philippines
Department of Education
 NATIONAL CAPITAL REGION
 SCHOOLS DIVISION OF PARAÑAQUE CITY
 BACLARAN ELEMENTARY SCHOOL UNIT-I

	Washed Sand	cu. m							
	Sub-Total								
D	Rebar Works								
	Footing	kg	42.7						
	Wall Footing	kg	29.6						
	Column	kg	32						
	Deformed Round Bars	kg	104						
	G.I Tia Wire	kg	3.00						
	Sub-Total								
E	Formworks								
	Column	sq.m	2.88						
	Coco Lumber	bd.ft	14.7						
	Plywood Ordinary, 1/4" x 4"x8'	pc	1.00						
	CWN, Assorted	kg	1.00						
	Subtotal								
	Masonry Works	sq.m	4.8						
5	CHB 4" thk	cu. m	60.00						
2	Portland Cement	bag	2.00						
2.1	Washed Sand	cu. m	1.00						
5	10mm x 6m RSB	cu. m	7.00						
3.1	G.I Tia Wire	cu. m	1.00						
	Plastering	sq.m	4.80						
2	Portland Cement	bag	2.00						
2.1	Washed Sand	cu. m	1.00						
	Sub-Total								
F2	Steel Works								
	G.I Pipe 3"O Sch. 50	pc	3.00						
	Tubular 50mm x 100 mm x 1.5mm	kg	185						
	Tubular 50mm x 150 mm x 1.5mm	kg	111						
	Flat Bar 1 x 6mm	kg	14.2						
	Welding Rod	kg	4.00						
	Sub-total								
	Roofing Works								
	Roof Installation	labor							
	Teckscrew	pc							
	Roof Sealant	L							
	Sub-Total								
E	Painting Works								
	Concrete Surfaces	sq.m	5.76						
	Neutralizer	gal	1.00						
	Latex Flat	gal	1.00						
	Masonry Putty	gal	1.00						
	Latex, Semi Gloss	gal	1.00						
	Acri Color	qrt	1.00						
	Steel Surface	sq.m							
	Red Oxide	gal	5.00						
	QDE	gal	5.00						
	Paint Thinner	gal	3.00						
	Sub-Total								
	Consumables								



Address: Pinaglabanan St., Baclaran, Parañaque City
Telephone No.: 8-853-93-50
Email: bes1.pque @deped.gov.ph



Republic of the Philippines
Department of Education
NATIONAL CAPITAL REGION
SCHOOLS DIVISION OF PARAÑAQUE CITY
BACLARAN ELEMENTARY SCHOOL UNIT-I

	Consumables (Painting matis, sand paper, cutting disc, rags, etc)	lot	1						
	Sub-Total								
	MATERIALS (VAT inclusive)								
	LABOR								
I.	DIRECT COST (I+II)								
II.	INDIRECT COST 22% OF (III)								
III.	TAX 5% OF (III + IV)								
IV.	TOTAL CONSTRUCTION COST (III + IV + V)								



Address: Pinaglabanan St., Baclaran, Parañaque City
Telephone No.: 8-853-93-50
Email: bes1.pque @deped.gov.ph