

Scope Narrative – USD 338 Parking Lot – 8th and Oak St – 1/10/2024

Valley Falls High School – East Parking Lot Reconstruction

Scope Narrative Below, intended to provide a more detailed understanding of the project requirements, and USD 338's preferred bid scope. Please contact Tom Brown with questions/concerns regarding document, or the bid process.

- Specific Scope Items
 - Remove existing asphalt (20' x 253' x 4").
 - Undercut soil 8".
 - Scarify and compact bottom 6" of undercut. Compact to KDOT Type A compaction.
 - Install new 6" fiber reinforce concrete pavement on 6" of AB3, doveled into existing concrete.
 - Drill and epoxy ½" tie bars into existing curb and valley gutter on 30" centers.
 - Sawcut new concrete pavement every 10' – 12'.
 - Seal all joints in new pavements.
 - Parking lot striping (27 stalls, 20' long by 9' wide, and two hashed areas).
 - Valley gutter, 28.5' long.
 - Alternates
 - Undercut soil 12".
 - 8" of asphalt on 8" of AB3.